

United States Environmental Protection Agency  
Washington, DC 20460

## Completion Form For Injection Wells

## Administrative Information

## 1. Permittee

Florence Copper Inc.

## Address (Permanent Mailing Address) (Street, City, and ZIP Code)

1575 W Hunt Hwy, Florence, AZ 85132

## 2. Operator

Florence Copper Inc.

## Address (Street, City, State and ZIP Code)

1575 W Hunt Hwy, Florence, AZ 85132

## 3. Facility Name

Florence Copper Inc.

## Telephone Number

(520) 374-3984

## Address (Street, City, State and ZIP Code)

1575 W Hunt Hwy, Florence, AZ 85132

## 4. Surface Location Description of Injection Well(s)

## State

Arizona

## County

Pinal

## Surface Location Description

Nw 1/4 of SW 1/4 of NE 1/4 of SW 1/4 of Section 28 Township 4S Range 9E

Locate well in two directions from nearest lines of quarter section and drilling unit

## Surface

Location 925 ft. from (N/S) N Line of quarter section  
and 1190 ft. from (E/W) E Line of quarter section.

## Well Activity

- ☐ Class I  
☐ Class II  
☐ Brine Disposal  
☐ Enhanced Recovery  
☐ Hydrocarbon Storage  
☒ Class III  
☐ Other

## Well Status

- ☒ Operating  
☐ Modification/Conversion  
☐ Proposed

## Type of Permit

- ☐ Individual  
☒ Area : Number of Wells 33

Lease Number NA

Well Number M56-LBF

Submit with this Completion Form the attachments listed in Attachments for Completion Form.

## Certification

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment (Ref. 40 CFR 144.32)

## Name and Official Title (Please type or print)

Ian Ream, Senior Hydrogeologist

## Signature

## Date Signed

9-12-2018

## PAPERWORK REDUCTION ACT

The public reporting and record keeping burden for this collection of information is estimated to average 49 hours per response for a Class I hazardous facility, and 47 hours per response for a Class I non-hazardous facility. Burden means the total time, effort, or financial resource expended by persons to generate, maintain, retain, or disclose or provide information to or for a Federal Agency. This includes the time needed to review instructions; develop, acquire, install, and utilize technology and systems for the purposes of collecting, validating, and verifying information, processing and maintaining information, and disclosing and providing information; adjust the existing ways to comply with any previously applicable instructions and requirements; train personnel to be able to respond to the collection of information; search data sources; complete and review the collection of information; and, transmit or otherwise disclose the information. An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB control number. Send comments on the Agency's need for this information, the accuracy of the provided burden estimates, and any suggested methods for minimizing respondent burden, including the use of automated collection techniques to Director, Collection Strategies Division, U.S. Environmental Protection Agency (2822), 1200 Pennsylvania Ave., NW, Washington, D.C. 20460. Include the OMB control number in any correspondence. Do not send the completed forms to this address.

### Attachments to be submitted with the Completion report:

#### I. Geologic Information

##### 1. Lithology and Stratigraphy

A. Provide a geologic description of the rock units penetrated by name, age, depth, thickness, and lithology of each rock unit penetrated.

B. Provide a description of the injection unit.

- (1) Name
- (2) Depth (drilled)
- (3) Thickness
- (4) Formation fluid pressure
- (5) Age of unit
- (6) Porosity (avg.)
- (7) Permeability
- (8) Bottom hole temperature
- (9) Lithology
- (10) Bottom hold pressure
- (11) Fracture pressure

C. Provide chemical characteristics of formation fluid (attach chemical analysis).

D. Provide a description of freshwater aquifers.

- (1) Depth to base of fresh water (less than 10,000 mg/l TDS).
- (2) Provide a geologic description of aquifer units with name, age, depth, thickness, lithology, and average total dissolved solids.

#### II. Well Design and Construction

1. Provide data on surface, intermediate, and long string casing and tubing. Data must include material, size, weight, grade, and depth set.
2. Provide data on the well cement, such as type/class, additives, amount, and method of emplacement.
3. Provide packer data on the packer (if used) such as type, name and model, setting depth, and type of annular fluid used.

4. Provide data on centralizers to include number, type and depth.

5. Provide data on bottom hole completions.

6. Provide data on well stimulation used.

#### III. Description of Surface Equipment

1. Provide data and a sketch of holding tanks, flow lines, filters, and injection pump.

#### IV. Monitoring Systems

1. Provide data on recording and nonrecording injection pressure gauges, casing-tubing annulus pressure gauges, injection rate meters, temperature meters, and other meters or gauges.

2. Provide data on constructed monitor wells such as location, depth, casing diameter, method of cementing, etc.

#### V. Logging and Testing Results

Provide a descriptive report interpreting the results of geophysical logs and other tests. Include a description and data on deviation checks run during drilling.

VI. Provide an as-built diagrammatic sketch of the injection well(s) showing casing, cement, tubing, packer, etc., with proper setting depths. The sketch should include well head and gauges.

VII. Provide data demonstrating mechanical integrity pursuant to 40 CFR 146.08.

VIII. Report on the compatibility of injected wastes with fluids and minerals in both the injection zone and the confining zone.

IX. Report the status of corrective action on defective wells in the area of review.

X. Include the anticipated maximum pressure and flow rate at which injection will operate.

**TECHNICAL MEMORANDUM**

17 September 2018  
File No. 129687-010

TO: Florence Copper Inc.  
Ian Ream, Senior Hydrogeologist

FROM: Haley & Aldrich, Inc.  
Lauren Candreva, R.G.

Subject: Drilling, Installation, and Integrity Testing Summary  
PTF Supplemental Monitoring Well M56-LBF  
Florence Copper Inc., Florence, Arizona



This document summarizes the drilling, installation, and testing of Production Test Facility (PTF) supplemental monitoring well M56-LBF for Florence Copper Inc. (Florence Copper) in Florence, Arizona, including the equipment used to perform the work, completion, and the results of well testing activities. Separate well completion reports have been created for each PTF well.

The Arizona Department of Water Resources Registry ID for well M56-LBF is 55-226795; the Well Registry Report is included in Appendix A. The well is located in the southeast quarter of the northwest quarter of the southwest quarter of Section 28 of Township 4 north, Range 9 East of the Gila and Salt River Baseline and Meridian (D(4-9)28CBD). The well is located within the Underground Injection Control (UIC) Permitted Area of Review (AOR) for UIC Permit R9UIC-AZ3-FY11-1 and was completed as a Class III supplemental monitoring well for the PTF (Figure 1).

Florence Copper contracted National Exploration, Wells, and Pumps (National) to drill, install, and test well M56-LBF in accordance with *Bid Specification: Installation, of Class III Monitoring Wells, Production Test Facility, Florence, Arizona* (Haley & Aldrich, Inc. [Haley & Aldrich], 2015). A Schramm T685WS drilling rig was used for all drilling and construction activities. Haley & Aldrich provided intermittent oversight of drilling activities and provided complete oversight during key activities such as geophysical logging, well installation, and testing. All reported depths are in feet below ground surface unless otherwise noted.

## I. Geologic Information

### 1. Lithology and Stratigraphy

#### A. Geology of Penetrated Units

The geology penetrated during the drilling of the Class III well M56-LBF is summarized below, and a lithologic log is included in Appendix B.

Lithologic Unit Name	Depth to Bottom of Unit (feet)	Thickness of Unit (feet)	Lithology and Age of Unit
Upper Basin Fill Unit (UBFU)	282	282	Alluvium; Quaternary to Tertiary
Middle Fine-Grained Unit (MFGU)	302	20	Alluvium; Tertiary
Lower Basin Fill Unit (LBFU)	Not encountered	>50	Alluvium; Tertiary to Cretaceous

#### B. Description of Injection Unit

Well M56-LBF is a supplemental monitoring well completed in the Lower Basin Fill Unit (LBFU). The bottom of the well is approximately 50 to 65 feet above the top of the permitted injection zone.

#### C. Chemical Characteristics of Formation Fluid

The chemical characteristics of the formation fluid in the injection zone are summarized below and are the sampling results from the center PTF wellfield well, R-09. The table below summarizes the primary chemical characteristics detected in a formation fluid sample collected on 23 April 2018; the complete analytical report is included in Appendix C.

Analyte	Result (mg/L)
<b>Metals</b>	
Aluminum	<0.08
Antimony	<0.005
Arsenic	0.0016
Barium	0.071
Beryllium	<0.0005
Cadmium	<0.00025
Calcium	140
Chromium	0.0051
Cobalt	<0.00025
Copper	0.011
Iron	<0.30
Lead	<0.0005
Magnesium	27
Manganese	0.002
Mercury	<0.001
Nickel	0.0033
Potassium	6.8



Analyte	Result (mg/L)
Selenium	<0.0025
Sodium	170
Thallium	<0.0005
Zinc	<0.04
<b>Anions</b>	
Bicarbonate	150
Chloride	310
Fluoride	<0.5
Nitrate	8.8
Sulfate	190
<b>Field Parameters</b>	
Total Dissolved Solids	1,000
pH	7.8
<b>Radiochemicals</b>	
Uranium	0.016
<b>Notes:</b> mg/L = milligrams per liter	

The water quality of each PTF monitoring well, including well M56-LBF, is summarized in *Procedures for Determining Alert Levels and Aquifer Quality Limits for Groundwater Compliance Monitoring* (Brown and Caldwell, 2018).

#### D. Description of Freshwater Aquifers

- 1) The depth to the base of the freshwater aquifer is defined by the interface where deeper formation fluid exhibits a total dissolved solids (TDS) value of 10,000 milligrams per liter (mg/L). The depth of the 10,000 mg/L interface is deeper than all of the wells drilled at the site and consequently has not been defined.
- 2) A geologic description of the aquifer units is included below:

Aquifer Unit Name	Age	Depth (feet)	Thickness (feet)	Lithology	Average Total Dissolved Solids <sup>1</sup> (mg/L)
UBFU	Quaternary/Tertiary	0 to 282	282	Alluvium	914
LBFU	Tertiary	Not encountered	Not encountered	Alluvium	754

<sup>1</sup> Average TDS values calculated from UBFU and LBFU monitoring well ambient monitoring results near the PTF.

## II. Well Design and Construction

### 1. Well M56-LBF Casing Installed

Casing	Material	Diameter (inches)	Weight (pounds per foot)	Depths	Borehole Diameter (inches)	Drilling Method
Surface	Mild steel	14 O.D. 13 $\frac{3}{8}$ I.D.	47.36	0 to 40	17 $\frac{1}{2}$	Conventional mud rotary
Well casing	Mild steel	5.66 O.D. 5.14 I.D.	5.40	-1.8 to 320	10 $\frac{3}{8}$	Conventional mud rotary
Screen	PVC Sch. 80 with 0.020-inch wide slots	5.56 O.D. 4.81 I.D.	4.08	320 to 340	10 $\frac{3}{8}$	Conventional mud rotary
<b>Notes:</b> <i>I.D. = inside diameter</i> <i>O.D. = outside diameter</i> <i>PVC = polyvinyl chloride</i> <i>Sch. = Schedule</i>						

### 2. Well Cement

Cement Interval	Cement Type	Additives	Amount Installed (cubic yards)	Method of Emplacement
Surface casing	Type V Neat 21 sack slurry	None	1.5 <sup>1</sup>	Submerged tremie
Well casing	Type V Neat 21 sack slurry	None	7.0	Submerged tremie
<sup>1</sup> Cement was mixed on-site and installed by drilling contractor, volume estimated.				

Field forms documenting pipe tallies, annular materials, and cement tickets are included in Appendix D.

### 3. Annular Packers

No annular packers were used during construction of well M56-LBF.

### 4. Centralizers

Casing	Centralizer Type	Number and Spacing
Well – FRP and PVC	Stainless steel – heavy duty	8 installed – every 40 feet
<b>Notes:</b> <i>FRP = fiberglass reinforced plastic</i> <i>PVC = polyvinyl chloride</i>		

5. Bottom Hole Completion

There is no bottom hole completion, as this is not an oil/gas well. The well was completed at the bottom with a stainless-steel endcap of the same diameter as the well screen.

6. Well Stimulation

No well stimulation was used during the drilling and construction of well M56-LBF.

### III. Description of Surface Equipment

1. Surface Equipment

Well M56-LBF is a supplemental monitoring well and has been equipped with a pressure transducer for monitoring water levels and a low-flow pump for collecting water quality samples. There is no surface equipment beyond the well casing stick-up and locking well vault. An as-built diagram of the well is included as Figure 2.

### IV. Monitoring Systems

1. Well Monitoring Equipment

Well M56-LBF is a monitoring well and does not have any monitoring systems for injection. A pressure transducer with a data logger is installed in the well to collect water levels for compliance reporting.

2. Monitoring Wells

A total of 16 monitoring wells (including well M56-LBF) are associated with the PTF: 7 point of compliance (POC) wells, 7 United States Environmental Protection Agency (USEPA) supplemental monitoring wells, and 2 operational monitoring wells. The POC wells are located outside the AOR and are not constructed as Class III wells. The supplemental monitoring and operational monitoring wells are located within the AOR and are constructed as Class III wells as required by the UIC Permit. The wells are summarized in the tables below by type.

POC Wells						
Well ID	Location X/Y (State Plane NAD 83)	Depth (feet)	Well Nom. Diameter (inches)	Cementing Method	Screened Interval (feet)	Screened Lithologic Unit
M14-GL	846750.23 746461.52	859	5 9/16 OD	Submerged tremie	778 to 838	LBFU
M15-GU	846697.17 746464.82	615	5 9/16 OD	Submerged tremie	554 to 594	LBFU

POC Wells						
Well ID	Location X/Y (State Plane NAD 83)	Depth (feet)	Well Nom. Diameter (inches)	Cementing Method	Screened Interval (feet)	Screened Lithologic Unit
M22-O	846751.26 746514.47	1,140	5 9/16 OD to 528 feet; 4½ OD to 1,140 feet	Submerged tremie	932 to 1,130	Oxide
M23-UBF	846688.13 746512.48	250	6¾ OD	Submerged tremie	210 to 250	UBFU
M52-UBF	851092.00 774178.00	274	5 9/16	Submerged tremie	198 to 273	UBFU
M54-LBF	847331.96 746682.61	630	5 9/16	Submerged tremie	310 to 629	LBFU
M54-O	847342.99 746702.36	1,199	5 9/16	Submerged tremie	668 to 1,198	Oxide
OD = outside diameter						

Supplemental Monitoring Wells						
Well ID	Location X/Y (State Plane NAD 83)	Depth (feet)	Well Nom. Diameter (inches)	Cementing Method	Screened Interval (feet)	Screened Lithologic Unit
M55-UBF	847541.46 746280.63	261	5	Submerged tremie	240 to 260	UBFU
M56-LBF	847518.70 746303.41	340	5	Submerged tremie	320 to 340	LBFU
M57-O	847378.37 746248.93	1,200	5	Submerged tremie	523 to 1,199	Oxide
M58-O	847672.23 746595.97	1,200	5	Submerged tremie	594 to 1,199	Oxide
M59-O	847934.95 746218.89	1,201	5	Submerged tremie	534 to 1,199	Oxide
M60-O	847599.37 745903.70	1,201	5	Submerged tremie	444 to 1,200	Oxide
M61-LBF	848184.46 746148.88	629	5	Submerged tremie	429 to 629	LBFU



Operational Monitoring Wells						
Well ID	Location X/Y (State Plane NAD 83)	Depth (feet)	Well Nom. Diameter (inches)	Cementing Method	Screened Interval	Screened Lithologic Unit
MW-01-LBF	847487.97 746360.54	444	5	Submerged tremie	330 to 440	LBFU
MW-01-O	847499.04 746369.31	1,200	5	Submerged tremie	500 to 1,200	Oxide

## V. Logging and Testing Results

Borehole geophysical logging was conducted on well M56-LBF in two phases: 1) open-hole surveys in the 12.25-inch borehole prior to installation of the well casing and screen, and 2) cased-hole surveys in the completed well.

The open-hole geophysical surveys completed at well M56-LBF included:

- Spontaneous potential;
- Natural gamma;
- Electrical resistivity (short and long normal);
- Caliper with calculated volume;
- Temperature;
- Sonic; and
- Deviation.

The cased-hole geophysical surveys completed included:

- Sonic;
- 4 pi density; and
- Dual density.

Open-hole geophysical surveys were used to support identification of the lithologic contacts, to evaluate the condition of the borehole, and to evaluate the deviation of the borehole.

The primary logs used to evaluate lithologic contacts were natural gamma ray, short (16-inch) and long (64-inch) normal electrical resistance, and single-point resistance.

The lithologic contacts for the Middle Fine-Grained Unit (MFGU) were selected based on the short and long resistance and the single-point resistance. All the resistivity values decreased and remained consistently low through the MFGU. This contact is generally characterized by a relatively sharp decrease in resistance at the top of the unit and a gradual increase in resistance below the bottom of the unit.

Cased-hole geophysical surveys were conducted to evaluate the cement seal and the casing-cement bond, to document baseline fluid temperature and conductivity, and to evaluate the plumbness of the well. The cement bond is discussed in Section VII.

Copies of all the geophysical logs are included in Appendix E; a figure summarizing the open-hole logs used to evaluate the geology is included as Figure 3.

## **VI. Well As-Built Diagram**

An as-built diagram for well M56-LBF is included as Figure 2.

## **VII. Demonstration of Mechanical Integrity**

A demonstration of Part I mechanical integrity of the well was completed using a standard annular pressure test (SAPT) in accordance with Part II.E.3.a.i.A of the UIC Permit. Mechanical integrity will be demonstrated every 2 years during operations. The SAPT for well M56-LBF is summarized below.

The SAPT was conducted by installing an inflatable packer in the well secured with a threaded well seal at the surface. The packer was installed near the bottom of the FRP-cased portion of the well and the wellhead was equipped with a water-tight threaded wellhead; the packer was inflated to form a seal against the casing. The bottom 5 feet of the packer drop pipe was perforated to allow for communication between the tubing and the annulus of the packer assembly. The drop pipe extended through the wellhead and a high pressure/low volume pump was attached to the drop pipe to pressurize the test interval. A valve on the drop pipe at the surface was used to isolate the test interval once the planned test pressure was achieved.

An In-Situ LevelTROLL® pressure transducer with a data logger was installed at the well head and connected to the packer assembly annulus interval via a National Pipe Thread adapter. The LevelTROLL was used to monitor and record pressure inside the well during the SAPT. To conduct the SAPT, water was pumped from a nearby well immediately prior to testing. Before the water was pumped into the test well, the water temperature was measured to ensure that it was similar to the ambient groundwater temperature of the test well to reduce the potential for differential temperature effects on the well casing. The SAPT for the Class III well was conducted by applying hydraulic pressure to the well casing and shutting in pressure between the packer and wellhead assembly, monitoring the shut-in pressure for a 30-minute period, then measuring the volume of water returned from the well casing after the pressure was released.

On 28 June 2017, the packer was installed to approximately 286 feet; the SAPT was unsuccessful. The USEPA SAPT form, a table of the data, and a chart of the data is provided in Appendix F.

Part II mechanical integrity is demonstrated by the cementing records included in this report (in accordance with Part II.E.3.ii.C of the UIC Permit) and will be demonstrated during operations by annular conductivity monitoring on the observation and multi-level sampling wells (in accordance with Part II.E.3.a.ii.A of the UIC Permit).

Cemented Interval	Cement Type	Calculated Grout Volume (cubic yards)	Installed Grout Volume (cubic yards)
Surface casing	Type V 21 sack neat cement slurry	0.9	1.5 <sup>1</sup>
Well casing	Type V 21 sack neat cement slurry	5.5	7.0
<sup>1</sup> Cement was mixed on-site and installed by drilling contractor, volume estimated.			

On 12 May 2017, density, sonic, and 4pi logs were run over the entire length of the completed well to verify the grout seal. Because the grouted interval is primarily unsaturated, a cement bond log tool was not run in well M56-LBF. A summary of the logs completed to demonstrate cement bond are included in Appendix G.

The cement bond of the steel casing at well M56-LBF was evaluated by the geophysical contractor by calculating a bond index; however, due to the limited saturated interval, density logs including focused density and 4pi density logs were also run to evaluate the unsaturated portion of the well. The bond index was calculated to be greater than 90 percent over the saturated cement grouted interval from approximately 246 to 283 feet. Below 283 feet, there is a decreased bond and density, but the density is relatively consistent. It is unclear why the density response of well M56-LBF changes through this zone. The grout volume installed exceeds the calculated grout volume for the well and the grout was installed in one lift with the tremie at the bottom of the grouted interval. The bond evaluation data is included on the summary log in Appendix G.

## VIII. Compatibility of Injected Waste

The Florence Copper Project is a Class III mineral extraction project and does not include the injection of any waste products of any kind. The injected fluid (lixiviant) is a carefully constituted in-situ copper recovery solution that will be recovered and recycled following injection.

The compatibility of the lixiviant was evaluated as part of the geochemical modeling completed by Florence Copper and summarized in the *Geochemical Evaluation to Forecast Composition of Process Solutions for In-Situ Copper Recovery Pilot Test Facility at Florence Copper, Florence Arizona* (Daniel B. Stephens Inc., 2014) which was included in Attachment H of the UIC Permit Application.

## IX. Status of Corrective Action on Defective Wells in the Area of Review

There are not currently any defective wells in the AOR.

## X. Maximum Pressures and Flow Rates for M56-LBF

Maximum Operating Pressure	Maximum Flow
Atmospheric	Not applicable – monitoring well

This well is a monitoring well used to monitor water quality near the PTF. No fluids will be injected.

## XI. Well Development

Well M56-LBF was initially developed by the airlift method, followed by pump development. Development activities were completed by National using a workover rig. On 21 April 2017, an airline was temporarily installed to 320 feet and airlift development of the well was conducted at approximately 10 gallons per minute (gpm) to purge drilling fluids and solids from the well. During airlift development, the airlift pump was turned on and off to surge the well. After 5.5 hours, approximately 1 gallon of AquaClear PFD® polymer dispersant was swabbed into the screened interval of the well. Airlift development was conducted for approximately 9 hours over a 4-day period. The discharge was turbid but sand-free at the end of the airlift development period.

To pump develop the well, on 26 April 2017 a submersible pump was temporarily installed to a depth of 335 feet. Prior to pumping, the static water level was approximately 236 feet. Pump development was conducted at approximately 19 gpm; the submersible pump was periodically turned off to surge the well during development. Pump development was conducted for a total of approximately 54 hours. The development was concluded on 1 May 2017, at which time the discharge was sand-free with turbidity values generally less than 10 Nephelometric Turbidity Units. Well development forms are included in Appendix H.

## XII. Well Completion

The surveyed location for well M56-LBF is as follows:

Northing (feet)	Easting (feet)	Measuring Point Elevation (feet amsl)
746303.41	847518.70	1478.65
<b>Notes:</b> <i>Northing and easting locations provided in State Plane North American Datum 1983; vertical location provided in North American Vertical Datum 1988. amsl = above mean sea level</i>		



### **XIII. Downhole Equipment**

Permanent equipment installed in well M56-LBF includes the following:

- QED® low-flow sampling pump hung on drop tubing (pump at 330 feet); and
- Pressure transducer.

The type and depth of equipment installed in each well is not constrained by the UIC Permit or the Aquifer Protection Permit (APP). This information is provided in accordance with Section 2.7.4.3 of the APP. Operational considerations may require that the type and depth of equipment be changed in response to conditions observed during operations.

### **XIV. References**

Brown and Caldwell, Inc., 2018. *Procedures for Determining Alert Levels and Aquifer Quality Limits for Groundwater Compliance Monitoring, Florence Copper Project, Florence, Arizona*. June.

Daniel B. Stephens, Inc., 2014. *Geochemical Evaluation to Forecast Composition of Process Solutions for In-Situ Copper Recovery Pilot Test Facility at Florence Copper, Florence Arizona*. Prepared for Florence Copper. May.

Haley & Aldrich, Inc., 2017. *Bid Specification: Installation, of Class III Monitoring Wells, Production Test Facility, Florence, Arizona*. Revised September 2017.



#### **Enclosures:**

- Figure 1 – Well Locations
- Figure 2 – M56-LBF Supplemental Monitoring Well As-Built Diagram
- Figure 3 – Geophysical Data and Lithologic Log
- Appendix A – Arizona Department of Water Resources Well Registry Report
- Appendix B – Lithologic Log
- Appendix C – Chemical Characteristics of Formation Water
- Appendix D – Well Completion Documentation
- Appendix E – Geophysical Logs
- Appendix F – SAPT Documentation
- Appendix G – Cement Bond Log Summary
- Appendix H – Well Development Field Forms

## FIGURES



GIS FILE PATH: G:\Projects\Florence Copper\129687 PTF Well Drilling\GIS\Maps\2018\_07129687\_010\_A001\_WELL\_LOCATIONS.mxd — USER: dfm — LAST SAVED: 7/17/2018 10:24:09 AM



**LEGEND**

- OBSERVATION WELL
- SUPPLEMENTAL MONITORING WELL
- POINT-OF-COMPLIANCE WELL

**PTF WELL**


- INJECTION
- RECOVERY
- WESTBAY WELL
- OPERATIONAL MONITORING

PTF WELL FIELD

STATE LAND LEASE

**NOTES**

1. ALL LOCATIONS AND DIMENSIONS ARE APPROXIMATE.
2. AERIAL IMAGERY SOURCE: ESRI



**HALEY  
ALDRICH**


FLORENCE COPPER PROJECT  
FLORENCE, ARIZONA

**WELL LOCATIONS**

**FLORENCE  
COPPER INC.** AUGUST 2018

**FIGURE 1**





#### NOTES

1. WELL REGISTRATION NO.: 55-226795
2. CADASTRAL LOCATION: D (4-9) 28 CBD
3. TOP OF CASING ELEVATION: 1478.65' AMSL
4. CONCRETE PAD ELEVATION: 1477.32' AMSL
5. I.D. = INSIDE DIAMETER
6. O.D. = OUTSIDE DIAMETER
7. PVC = POLYVINYL CHLORIDE



PRODUCTION TEST FACILITY  
FLORENCE COPPER, INC.  
FLORENCE, ARIZONA


### M56-LBF SUPPLEMENTAL MONITORING WELL AS-BUILT DIAGRAM



SCALE: NOT TO SCALE  
SEPTEMBER 2018

FIGURE 2





**HALEY  
ALDRICH**

PRODUCTION TEST FACILITY  
FLORENCE COPPER, INC.  
FLORENCE, ARIZONA

**FLORENCE  
COPPER**

M56-LBF SUPPLEMENTAL MONITORING  
WELL GEOPHYSICAL DATA AND  
LITHOLOGIC LOG

SCALE: AS SHOWN  
SEPTEMBER 2018

FIGURE 3

## **APPENDIX A**

### **Arizona Department of Water Resources Well Registry Report**



Arizona Department of Water Resources  
Information Management Unit  
PO Box 36020 • Phoenix, Arizona 85067-6020  
(602) 771-8527 • 602-771-8500

# Well Driller Report and Well Log

9/20/17

THIS REPORT MUST BE FILED WITHIN 30 DAYS OF COMPLETING THE WELL.

PLEASE PRINT CLEARLY USING BLACK OR BLUE INK

FILE NUMBER
D(4-9) 28 CBD
WELL REGISTRATION NUMBER
55 - 226795
PERMIT NUMBER (IF ISSUED)

## SECTION 1. DRILLING AUTHORIZATION

### Drilling Firm

Mail To:	NAME	DWR LICENSE NUMBER
	NATIONAL EWP, INC.	823
	ADDRESS	TELEPHONE NUMBER
	1200 W. SAN PEDRO ST.	480-558-3500
	CITY / STATE / ZIP	FAX
	GILBERT, AZ, 85233	

## SECTION 1. REGISTRY INFORMATION

### Well Owner

FULL NAME OF COMPANY, ORGANIZATION, OR INDIVIDUAL  
FLORENCE COPPER, INC.

### Mailing Address

1575 W. HUNT HWY

### CITY / STATE / ZIP

FLORENCE, AZ, 85132

### CONTACT PERSON NAME AND TITLE

Ian Ream, Sr. Hydrauliclogis

### TELEPHONE NUMBER

520 374-3984

### FAX

### WELL NAME (e.g., MW-1, PZ-3, lot 25 Well, Smith Well, etc.)

M56-LBF

### Location of Well

#### WELL LOCATION ADDRESS (IF ANY)

Same as well owner

TOWNSHIP (N/S)	RANGE (E/W)	SECTION	160 ACRE	40 ACRE	10 ACRE
4S	9E	28	SW 1/4	NW 1/4	SE 1/4
LATITUDE			LONGITUDE		
33	3	2 N	111	26	7 W

#### METHOD OF LATITUDE/LONGITUDE (CHECK ONE)

☒ \*GPS: Hand-Held  
☐ USGS Quad Map ☐ Conventional Survey ☐ \*GPS: Survey-Grade

#### LAND SURFACE ELEVATION AT WELL

1478

Feet Above Sea Level

#### METHOD OF ELEVATION (CHECK ONE)

☒ \*GPS: Hand-Held  
☐ USGS Quad Map ☐ Conventional Survey ☐ \*GPS: Survey-Grade

#### \*IF GPS WAS USED, GEOGRAPHIC COORDINATE DATUM (CHECK ONE)

☒ NAD-83 ☐ Other (please specify)

#### COUNTY

Pinal

#### ASSESSOR'S PARCEL ID NUMBER (MOST RECENT)

BOOK	MAP	PARCEL
0	0	0

## SECTION 3. WELL CONSTRUCTION DETAILS

### Drilling Method

#### CHECK ONE

- ☐ Air Rotary  
☐ Bored or Augered  
☐ Cable Tool  
☐ Dual Rotary  
☒ Mud Rotary  
☐ Reverse Circulation  
☐ Driven  
☐ Jetted  
☐ Air Percussion / Odex Tubing  
☐ Other (please specify)

### Method of Well Development

#### CHECK ONE

- ☒ Airlift  
☐ Bail  
☐ Surge Block  
☐ Surge Pump  
☐ Other (please specify)

### Condition of Well

#### CHECK ONE

- ☐ Capped  
☒ Pump Installed

### Method of Sealing at Reduction Points

#### CHECK ONE

- ☒ None  
☐ Packed  
☐ Swedged  
☐ Welded  
☐ Other (please specify)

### Construction Dates

#### DATE WELL CONSTRUCTION STARTED

4.14.2017

#### DATE WELL CONSTRUCTION COMPLETED

4.14.2017

I state that this notice is filed in compliance with A.R.S. § 45-596 and is complete and correct to the best of my knowledge and belief.

SIGNATURE OF QUALIFYING PARTY

DATE

8-3-17



WELL REGISTRATION NUMBER  
55 - 226795

### Depth

DEPTH OF BORING

352

Feet Below Land Surface

DEPTH OF COMPLETED WELL

340

Feet Below Land Surface

[illegible]

235

Feet Below Land Surface

DATE MEASURED

4.30.2017

TIME MEASURED

12:00

IF FLOWING WELL, METHOD OF FLOW REGULATION

☐ Valve      ☐ Other:[illegible]

## ANNULAR MATERIAL TYPE (T)

**FILTER PACK**

[illegible]



1

WELL REGISTRATION NUMBER  
55 - 226795

## SECTION 5. GEOLOGIC LOG OF WELL

[illegible]

# Well Driller Report and Well Log

WELL REGISTRATION NUMBER  
55 - 226795

## SECTION 6. WELL SITE PLAN

NAME OF WELL OWNER

FLORENCE COPPER, INC.



COUNTY ASSESSOR'S PARCEL ID NUMBER (MOST RECENT)

BOOK

MAP

PARCEL

- ❖ Please draw the following: (1) the boundaries of property on which the well was located; (2) the well location; (3) the locations of all septic tank systems and sewer systems on the property or within 100 feet of the well location, even if on neighboring properties; and (4) any permanent structures on the property that may aid in locating the well.
- ❖ Please indicate the distance between the well location and any septic tank system or sewer system.

							
							1" = _____ ft
							

Run Date: 01/13/2017

**AZ DEPARTMENT OF WATER RESOURCES**  
**WELL REGISTRY REPORT - WELLS55**

---

Location	D	4.0	9.0	28	C	B	D	Well Reg.No	55 - 226795	AMA	PINAL	AMA
----------	---	-----	-----	----	---	---	---	-------------	-------------	-----	-------	-----

Registered Name	FLORENCE COPPER, INC. 1575 W. HUNT HWY	File Type	NEW WELLS (INTENTS OR APPLICATIONS)
	FLORENCE	Application/Issue Date	01/11/2017
	AZ 85132		

Owner	OWNER	Well Type	ENV - MONITOR
Driller No.	823	SubBasin	ELOY
Driller Name	NATIONAL EWP, INC.	Watershed	UPPER GILA RIVER
Driller Phone	480-558-3500	Registered Water Uses	MONITORING
County	PINAL	Registered Well Uses	MONITOR
		Discharge Method	NO DISCHARGE METHOD LISTED
Intended Capacity GPM	0.00	Power	NO POWER CODE LISTED

Well Depth	0.00	Case Diam	0.00	Tested Cap	0.00
Pump Cap.	0.00	Case Depth	0.00	CRT	
Draw Down	0.00	Water Level	0.00	Log	
		Acres Irrig	0.00	Finish	NO CASING CODE LISTED

Contamination Site: NO - NOT IN ANY REMEDIAL ACTION SITE

Tribe: Not in a tribal zone

Comments Well M56-LBF  
Landownership: AZ State Land Dept. (Mineral Lease #11-026500)  
TV

Current Action

1/13/2017	555	DRILLER & OWNER PACKETS MAILED
Action Comment: TNV		

Action History

1/13/2017	550	DRILLING AUTHORITY ISSUED
Action Comment: TNV		
1/11/2017	155	NOI RECEIVED FOR A NEW NON-PRODUCTION WELL
Action Comment: TNV		

ARIZONA DEPARTMENT OF WATER RESOURCES  
1110 W. Washington St. Suite 310  
Phoenix, Arizona 85007

THIS AUTHORIZATION SHALL BE IN POSSESSION OF THE DRILLER DURING ALL DRILLING OPERATIONS

WELL REGISTRATION NO: 55-226795

AUTHORIZED DRILLER: NATIONAL EWP, INC.

LICENSE NO: 823

NOTICE OF INTENTION TO DRILL ENV - MONITOR WELL(S) HAS BEEN FILED WITH THE DEPARTMENT BY:

WELL OWNER: FLORENCE COPPER, INC. 1575 W. HUNT HWY FLORENCE, AZ, 85132

THE WELL(S) IS/ARE TO BE LOCATED IN THE:

SE 1/4 of the NW 1/4 of the SW 1/4 Section 28 Township 4.0 SOUTH Range 9.0 EAST

NO. OF WELLS IN THIS PROJECT: 1

THIS AUTHORIZATION EXPIRES AT MIDNIGHT ON THE DAY OF January 11, 2018

*Sella Muriello*

GROUNDWATER PERMITTING AND WELLS

THE DRILLER MUST FILE A LOG OF THE WELL WITHIN 30 DAYS OF COMPLETION OF DRILLING.





ARIZONA DEPARTMENT of WATER RESOURCES  
1110 W. Washington St. Suite 310  
Phoenix, AZ 85007  
602-771-8500  
azwater.gov



DOUGLAS A. DUCEY  
Governor

THOMAS BUSCHATZKE  
Director

January 13, 2017

FLORENCE COPPER, INC.  
1575 W. HUNT HWY  
FLORENCE, AZ 85132

Registration No. 55- 226795  
File Number: D(4-9) 28 CBD

Dear Well Applicant:

Enclosed is a copy of the Notice of Intention to Drill (NOI) a well which you or your driller recently filed with the Department of Water Resources. This letter is to inform you that the Department has approved the NOI and has mailed, or made available for download, a drilling authorization card to your designated well drilling contractor. The driller may not begin drilling until he/she has received the authorization, and must keep it in their possession at the well site during drilling. Although the issuance of this drill card authorizes you to drill the proposed well under state law, the drilling of the well may be subject to restrictions or regulations imposed by other entities.

Well drilling activities must be completed within one year after the date the NOI was filed with the Department. If drilling is not completed within one year, a new NOI must be filed and authorization from this Department received before proceeding with drilling. If the well cannot be successfully completed as initially intended (dry hole, cave in, lost tools, etc.), the well must be properly abandoned and a Well Abandonment Completion Report must be filed by your driller [as required by A.A.C. R12-15-816(F)].

If you change drillers, you must notify the Department of the new driller's identity on a Request to Change Well Information (form 55-71A). Please ensure that the new driller is licensed by the Department to drill the type of well you require. A new driller may not begin drilling until he/she receives a new drilling authorization card from the Department.

If you find it necessary to change the location of the proposed well(s), you may not proceed with drilling until you file an amended NOI with the Department. An amended drilling authorization card will then be issued to the well drilling contractor, which must be in their possession before drilling begins.

Arizona statute [A.R.S. § 45-600] requires registered well owners to file a Pump Installation Completion Report (form 55-56) with the Department within 30 days after the installation of pumping equipment, if authorized. A blank report is enclosed for your convenience. State statute also requires the driller to file a complete and accurate Well Drillers Report and Well Log (form 55-55) within 30 days after completion of drilling. A blank report form was provided to your driller with the drilling authorization card. You should insist and ensure that all of the required reports are accurately completed and timely filed with the Department.

Please be advised that Arizona statute [A.R.S. § 45-593(C)] requires a registered well owner to notify the Department of a change in ownership of the well and/or information pertaining to the physical characteristics of the well in order to keep this well registration file current and accurate. Any change in well information or a request to change well driller must be filed on a Request to Change Well Information form (form 55-71A) that may be downloaded from the ADWR Internet website at [www.azwater.gov](http://www.azwater.gov).

Sincerely,

Groundwater Permitting and Wells Section

<b>Arizona Department of Water Resources</b> Groundwater Permitting and Wells Section P.O. Box 36020 Phoenix, Arizona 85067-6020 (602) 771-8500 • (602) 771-8690 • <a href="http://www.azwater.gov">www.azwater.gov</a> •	<b>Notice of Intent to Drill, Deepen, or Modify a Monitor / Piezometer / Environmental Well</b>	<b>\$150 FEE</b>
---	---	----------------------

- ❖ Review instructions prior to completing form in black or blue ink.
  - ❖ You must include with your Notice:
    - \$150 check or money order for the filing fee.
    - Well construction diagram, labeling all specifications listed in Section 6 and Section 7.
- Authority for fee: A.R.S. § 45-596 and A.A.C. R12-15-104.

AMA / INA <i>Pinal</i>	B <i>PIN 11</i>	FILE NUMBER <i>24928 CBD</i>
RECEIVED DATE <i>1/11/2017</i>	WS <i>08 UGR</i>	WELL REGISTRATION NUMBER <i>55 - 226795</i>
ISSUED DATE <i>1/13/2017</i>	REMEDIAL ACTION SITE <i>000</i>	

### SECTION 1. REGISTRY INFORMATION

To determine the location of well, please refer to the Well Registry Map (<https://gisweb.azwater.gov/WellRegistry/Default.aspx>) and/or Google Earth (<http://www.earthpoint.us/Townships.aspx>)

Well Type	Proposed Action	Location of Well																		
CHECK ONE <input checked="" type="checkbox"/> Monitor <input type="checkbox"/> Piezometer <input type="checkbox"/> Vadose Zone <input type="checkbox"/> Air Sparging <input type="checkbox"/> Soil Vapor Extraction <input type="checkbox"/> Other (please specify):	CHECK ONE <input checked="" type="checkbox"/> Drill New Well <input type="checkbox"/> Deepen <input type="checkbox"/> Modify  WELL REGISTRATION NUMBER (if Deepening or Modifying) 55 -	WELL LOCATION ADDRESS (IF ANY)  <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 16.6%;">TOWNSHIP(N/S)</td> <td style="width: 16.6%;">RANGE (E/W)</td> <td style="width: 16.6%;">SECTION</td> <td style="width: 16.6%;">160 ACRE</td> <td style="width: 16.6%;">40 ACRE</td> <td style="width: 16.6%;">10 ACRE</td> </tr> <tr> <td>4.0 S</td> <td>9.0 E</td> <td>28</td> <td>SW ¼</td> <td>NW ¼</td> <td>SE ¼</td> </tr> </table> COUNTY ASSESSOR'S PARCEL ID NUMBER <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 33.3%;">BOOK</td> <td style="width: 33.3%;">MAP</td> <td style="width: 33.3%;">PARCEL</td> </tr> <tr> <td></td> <td></td> <td>1001</td> </tr> </table> COUNTY WHERE WELL IS LOCATED PINAL	TOWNSHIP(N/S)	RANGE (E/W)	SECTION	160 ACRE	40 ACRE	10 ACRE	4.0 S	9.0 E	28	SW ¼	NW ¼	SE ¼	BOOK	MAP	PARCEL			1001
TOWNSHIP(N/S)	RANGE (E/W)	SECTION	160 ACRE	40 ACRE	10 ACRE															
4.0 S	9.0 E	28	SW ¼	NW ¼	SE ¼															
BOOK	MAP	PARCEL																		
		1001																		

### SECTION 2. OWNER INFORMATION

Land Owner	Well Owner (check this box if Land Owner and Well Owner are same <input type="checkbox"/> )
FULL NAME OF COMPANY, ORGANIZATION, OR INDIVIDUAL AZ State Land Dept (Mineral Lease # 11-026500)	FULL NAME OF COMPANY, GOVERNMENT AGENCY, OR INDIVIDUAL Florence Copper, Inc. <span style="color: blue; font-weight: bold;">RECEIVED</span>
MAILING ADDRESS 1616 W Adams St	MAILING ADDRESS 1575 W Hunt Hwy
CITY / STATE / ZIP CODE Phoenix, AZ 85007	CITY / STATE / ZIP CODE Florence, AZ 85132 <span style="color: red; font-weight: bold;">JAN 11 2017</span>
CONTACT PERSON NAME AND TITLE Lisa Atkins, State Land Commissioner	CONTACT PERSON NAME AND TITLE Ian Ream, Senior Hydrogeologist <span style="color: blue; font-weight: bold;">ADWR</span>
TELEPHONE NUMBER (602) 542-4631	TELEPHONE NUMBER (520) 374-3984
FAX	FAX (520) 374-3999

### SECTION 3. DRILLING AUTHORIZATION

Drilling Firm	Consultant (if applicable)
NAME National EWP	CONSULTING FIRM Haley & Aldrich, Inc.
DWR LICENSE NUMBER 823	CONTACT PERSON NAME Mark Nicholls
TELEPHONE NUMBER (480) 558-3540	TELEPHONE NUMBER 602-760-2423
FAX 480-558-3525	FAX 602-760-2448
EMAIL ADDRESS jstephens@nationalewp.com	EMAIL ADDRESS mnicholls@haleyaldrich.com

### SECTION 4.

Questions	Yes	No	Explanation:
1. Are all annular spaces between the casing(s) and the borehole for the placement of grout at least 2 inches?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	2-inch annular spaces are special standards required for wells located in and near groundwater contamination sites (such as CERCLA, WQARF, DOD, LUST).
2. Is the screened or perforated interval of casing greater than 100 feet in length?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	100-foot maximum screen intervals are a special standard for wells located in and near groundwater contamination sites (such as CERCLA, WQARF, DOD, LUST).
3. Are you requesting a variance to use thermoplastic casing in lieu of steel casing in the surface seal?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	The wells must be constructed in a vault. Pursuant to A.A.C. R12-15-801 (27) a "vault" is defined as a tamper-resistant watertight structure used to complete a well below the land surface.
4. Is there another well name or identification number associated with this well? (e.g., MW-1, P22, 06-04, etc.)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	If yes, please state <b>M56-LBF</b>
5. Have construction plans been coordinated with the Arizona Department of Environmental Quality?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	If yes, please state agency contact & phone number <b>David Haaq, 602-771-4669</b>
6. For monitor wells, is dedicated pump equipment to be installed?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	If yes, please state design pump capacity (Gallons per Minute) <b>Low-flow</b>
7. Is this well a new well located in an Active Management Area AND intended to pump water for the purpose of remediating groundwater?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	You must also file a supplemental form A.R.S. § 45-454(c) & (f) unless the well is a replacement well and the total number of operable wells on the site is not increasing. (See instructions)
8. Will the well registration number be stamped on the vault cover or on the upper part of the casing?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	If no, where will the registration number be placed?



Notice of Intent to Drill, Deepen, or Modify a *Monitor / Piezometer / Environmental Well*

WELL REGISTRATION NUMBER  
55 - 226795

**SECTION 6. WELL CONSTRUCTION DETAILS**

<b>Drill Method</b> CHECK ONE <input type="checkbox"/> Air Rotary <input type="checkbox"/> Bored or Augered <input type="checkbox"/> Cable Tool <input type="checkbox"/> Dual Rotary <input checked="" type="checkbox"/> Mud Rotary <input type="checkbox"/> Reverse Circulation <input type="checkbox"/> Driven <input type="checkbox"/> Jetted <input type="checkbox"/> Air Percussion / Odex Tubing <input type="checkbox"/> Other (please specify):		<b>Method of Well Development</b> CHECK ONE <input checked="" type="checkbox"/> Airlift <input type="checkbox"/> Bail <input type="checkbox"/> Surge Block <input type="checkbox"/> Surge Pump <input type="checkbox"/> Other (please specify):		<b>Grout Emplacement Method</b> CHECK ONE <input checked="" type="checkbox"/> Tremie Pumped (Recommended) <input type="checkbox"/> Gravity <input type="checkbox"/> Pressure Grout <input type="checkbox"/> Other (please specify):	
<b>DATE CONSTRUCTION TO BEGIN</b> 01/16/2017		<b>Method of Sealing at Reduction Points</b> CHECK ONE <input checked="" type="checkbox"/> None <input type="checkbox"/> Welded <input type="checkbox"/> Swedged <input type="checkbox"/> Packed <input type="checkbox"/> Other (please specify):		<b>Surface or Conductor Casing</b> CHECK ONE <input type="checkbox"/> Flush Mount in a vault <input checked="" type="checkbox"/> Extends at least 1' above grade	

**SECTION 7. PROPOSED WELL CONSTRUCTION PLAN** (attach additional page if needed)

Attach a well construction diagram labeling all specifications below.

Borehole			Casing														
DEPTH FROM SURFACE		BOREHOLE DIAMETER (inches)	DEPTH FROM SURFACE		OUTER DIAMETER (inches)	MATERIAL TYPE ( T )				PERFORATION TYPE ( T )						SLOT SIZE IF ANY (inches)	
FROM (feet)	TO (feet)		FROM (feet)	TO (feet)		STEEL	PVC	ABS	IF OTHER TYPE, DESCRIBE	BLANK OR NONE	WIRE WRAP	SHUTTER SCREEN	MILLS	KNIFE	SLOTTED		IF OTHER TYPE, DESCRIBE
0	20	20	0	20	14	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
0	350	10.5	0	320	5	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
			320	340	5	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		0.020

**Annular Material**

DEPTH FROM SURFACE		ANNULAR MATERIAL TYPE ( T )								FILTER PACK		
FROM (feet)	TO (feet)	NONE	CONCRETE	NEAT CEMENT OR CEMENT GROUT	CEMENT-BENTONITE GROUT	BENTONITE GROUT	CHIPS	PELLETS	IF OTHER TYPE OF ANNULAR MATERIAL DESCRIBE	SAND	GRAVEL	SIZE
0	300	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	
300	310	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	Fine sand
310	350	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	No. 8-12


IF THIS WELL HAS NESTED CASINGS, SPECIFY NUMBER OF CASING STRINGS  
 EXPECTED DEPTH TO WATER (Feet Below Ground Surface)  
 211

**SECTION 8. PERMISSION TO ACCESS**

☐ By checking this box, I hereby provide ADWR permission to enter the property for the purpose of taking water level measurements at this well. (See instructions.)

**SECTION 9. LAND OWNER AND WELL OWNER SIGNATURE**

I state that this notice is filed in compliance with A.R.S. § 45-596 and is complete and correct to the best of my knowledge and

Land Owner	Well Owner (if different from Land Owner; See instructions)
PRINT NAME AND TITLE	PRINT NAME AND TITLE Ian Ream, Senior Hydrogeologist
SIGNATURE OF LAND OWNER	SIGNATURE OF WELL OWNER 
DATE	DATE Jan 9, 2017
<input type="checkbox"/> By checking this box, you agree to allow ADWR to contact you via electronic mail.	<input checked="" type="checkbox"/> By checking this box, you agree to allow ADWR to contact you via electronic mail.
EMAIL ADDRESS	EMAIL ADDRESS IanReam@florencecopper.com


**SECTION 5. Well Construction Diagram**

Provide a well construction diagram showing all existing well construction features listed in Section 6 and Section 7.

See attached well diagram.



SS-226745



MOBIL, CITTA  
G:\PROJECTS\CURIS RESOURCES\38706-CURIS FEASIBILITY\DRAWINGS\M56-LBF\_WELL.DWG  
Printed: 6/26/2015 2:14 PM Layout: M56-LBF

HALEY  
ALDRICH

FLORENCE COPPER, INC.  
FLORENCE, ARIZONA


M56-LBF  
WELL CONSTRUCTION DIAGRAM

FLORENCE  
COPPER INC.


SCALE: NOT TO SCALE

FIGURE 1









20

200310240

21

20031018E

20031018N

22

20031054B

21101010A

USA200060

PINAL AMA

200310450

20035007

20035002B

20031054A

200310470

28

27

29

20035003

T 4S  
R 9E

ARIZONA

20031019E

20035006A

200310200

200370010

20038001A

32

33

20038001B

20031019C

34

20037013A

200380020

20031019D

20031019D

20031019D



## Torren Valdez

---

**From:** Ian Ream <IanReam@florencecopper.com>  
**Sent:** Friday, January 13, 2017 9:06 AM  
**To:** Torren Valdez  
**Subject:** Re: Map of monitor well locations

Hi Torren,

The pumps will be QED micro purge. They typically do a liter or two a minute. Very low flow. Looking for discreet interval samples. The flow rate is based on drawdown. The goal is not to draw down the well much more than a half a foot or 1 foot.

Thanks,

Ian Ream  
Senior Hydrogeologist  
Florence Copper

On Jan 13, 2017, at 8:56 AM, Torren Valdez <[tvaldez@azwater.gov](mailto:tvaldez@azwater.gov)> wrote:

Ian,

Would you happen to know the pump capacity (gpm) for the low-flow pumps that will be installed on those monitoring wells?

Thank you,

**Torren Valdez**  
Water Planning & Permitting Division  
Arizona Department of Water Resources  
602.771.8614

<image002.jpg>

---

**From:** Ian Ream [<mailto:IanReam@florencecopper.com>]  
**Sent:** Thursday, January 12, 2017 11:13 AM  
**To:** Torren Valdez <[tvaldez@azwater.gov](mailto:tvaldez@azwater.gov)>  
**Subject:** Map of monitor well locations

Hi Torren,

Here is a map with the well locations.

Please don't hesitate to contact me if you need anything else or have any questions.

Cheers,

Ian

**Ian Ream** Senior Hydrogeologist

<image003.jpg>

Florence Copper Inc.

1575 W. Hunt Highway Florence AZ USA 85132

C 520-840-9604 T 520-374-3984 F 520-374-3999

E [ianream@florencecopper.com](mailto:ianream@florencecopper.com) Web [florencecopper.com](http://florencecopper.com)

---

**\*Notice Regarding Transmission**

This message is intended only for the person(s) to whom it is addressed and may contain information that is privileged and confidential. If you are not the intended recipient, you are hereby notified that any dissemination or copying of this communication is prohibited. Please notify us of the error in communication by telephone (778-373-4533) or by return e-mail and destroy all copies of this communication. Please note that any views or opinions presented in this email are solely those of the author and do not necessarily represent those of Taseko Mines Limited or any affiliated or associated company. The recipient should check this email and any attachments for the presence of viruses. Neither Taseko Mines Limited nor any affiliated or associated company accepts any liability for any damage caused by any virus transmitted by this email. Thank you."

---

**\*Notice Regarding Transmission**

This message is intended only for the person(s) to whom it is addressed and may contain information that is privileged and confidential. If you are not the intended recipient, you are hereby notified that any dissemination or copying of this communication is prohibited. Please notify us of the error in communication by telephone (778-373-4533) or by return e-mail and destroy all copies of this communication. Please note that any views or opinions presented in this email are solely those of the author and do not necessarily represent those of Taseko Mines Limited or any affiliated or associated company. The recipient should check this email and any attachments for the presence of viruses. Neither Taseko Mines Limited nor any affiliated or associated company accepts any liability for any damage caused by any virus transmitted by this email. Thank you."

## NOTICE

A.R.S. § 41-1030(B), (D), (E) and (F) provide as follows:

- B. An agency shall not base a licensing decision in whole or in part on a licensing requirement or condition that is not specifically authorized by statute, rule or state tribal gaming compact. A general grant of authority in statute does not constitute a basis for imposing a licensing requirement or condition unless a rule is made pursuant to that general grant of authority that specifically authorizes the requirement or condition.
- D. This section may be enforced in a private civil action and relief may be awarded against the state. The court may award reasonable attorney fees, damages and all fees associated with the license application to a party that prevails in an action against the state for a violation of this section.
- E. A state employee may not intentionally or knowingly violate this section. A violation of this section is cause for disciplinary action or dismissal pursuant to the agency's adopted personnel policy.
- F. This section does not abrogate the immunity provided by section 12-820.01 or 12-820.02.

ARIZONA DEPARTMENT of WATER RESOURCES  
1110 W. Washington St. Suite 310  
Engineering and Permits Division  
Phoenix, AZ 85007  
602-771-8500

**NOTICE TO WELL DRILLERS**

**This is a reminder that a valid drill card be present for the drilling of each and every well constructed on a site.\* The problem seems to occur during the construction of a well when an unexpected problem occurs. Either the hole collapses, the hole is dry, a drill bit is lost and can't be recovered, or any number of other situations where the driller feels that he needs to move over and start another well. If you encounter this type of scenario, please be aware drillers do not have the authority to start another well without first obtaining drilling authority for the new well. Please note the following statutes and regulations pertaining to well drilling and construction:**

**ARIZONA REVISED STATUTE (A.R.S.)**

**A.R.S. § 45-592.A.**

**A person may construct, replace or deepen a well in this state only pursuant to this article and section 45-834.01. The drilling of a well may not begin until all requirements of this article and section 45-834.01, as applicable, are met.**

**\*\*\***

**A.R.S. § 594.A.**

**The director shall adopt rules establishing construction standards for new wells and replacement wells, the deepening and abandonment of existing wells and the capping of open wells.**

**\*\*\***

**A.R.S. § 600.A**

**A well driller shall maintain a complete and accurate log of each well drilled.**

**ARIZONA ADMINISTRATIVE CODE (A.A.C.)**

**A.A.C. R12-15-803.A.**

**A person shall not drill or abandon a well, or cause a well to be drilled or abandoned, in a manner which is not in compliance with A.R.S. Title 45, Chapter 2, Article 10, and the rules adopted thereunder.**

**\*\*\***

**A.A.C. R12-15-810.A.**

**A well drilling contractor or single well licensee may commence drilling a well only if the well drilling contractor or licensee has possession of a drilling card at the well site issued by the Director in the name of the well drilling contractor or licensee, authorizing the drilling of the specific well in the specific location.**

**\*\*\***

**A.A.C. R12-15-816.F.**

**In the course of drilling a new well, the well may be abandoned without first filing a notice of intent to abandon and without an abandonment card.**

**\* THIS REQUIREMENT DOES NOT PERTAIN TO THE DRILLING OF MINERAL EXPLORATION,  
GEOTECHNICAL OR HEAT PUMP BOREHOLES**



## Transaction Receipt - Success

Arizona Water Resources  
Arizona Water Resources  
MID:347501639533  
1700 W Washington St  
Phoenix , AZ 85012  
602-771-8454

---

01/11/2017 04:20PM  
Remittance ID  
Arizona011117181536095Ald  
Transaction ID:  
178069995

---

KELSEY SHERRARD  
500 Maint St  
WOODLAND, California 95695  
United States  
Visa - 3420  
Approval Code: 040691

---

Sale  
Amount: \$1,800.00

---

55-226788, 55-226789, 55-226790, 55-226791, 55-226792, 55-226793, 55-226794, 55-226795, 55-226796, 55-226797, 55-226798, 55-226799

N/A


Cash Reciepts

0

palder@azwater.gov

---

Cardmember acknowledges  
receipt of goods and/or  
services in the amount of  
the total shown hereon and  
agrees to perform the  
obligations set forth by the  
cardmember's agreement with  
the issuer.

Signature   
[click here](#) to continue.

**Arizona Department of Water Resources**

1110 West Washington Street, Suite 310

Phoenix AZ 85007

**Customer:**

KELSEY SHERRARD  
500 MAIN STREET  
WOODLAND, CA 95695

Receipt #: 17-49315  
Office: MAIN OFFICE  
Receipt Date: 01/11/2017  
Sale Type: Mail  
Cashier: WRPXA

Item No.	Function Code	AOBJ	Description	Ref ID	Qty	Unit Price	Ext Price
8505	122221	4439-6F	MONITOR, PIEZOMETER, AIR SPARGING, SOIL VAPOR EXTR		12	150.00	1,800.00
RECEIPT TOTAL:							1,800.00

Payment type: CREDIT CARD

Amount Paid: \$1,800.00

Authorization 178069995

Payment Received Date: 01/11/2017


Notes: Credit card payment for \$1,800.00 is for well registration numbers 55-226788, 55-226789, 55-226790, 55-226791, 55-226792, 55-226793, 55-226794, 55-226795, 55-226796, 55-226797, 55-226798, 55-226799

## **APPENDIX B**

### **Lithologic Log**

Oct 3, 17

H&amp;A-SONIC-129687-ELEVATION HA-LIB09 WITH COMMENTS GLB HA-DIRECT PUSH + SONIC LOG GDT G:\PROJECTS\CURIS RESOURCES\129687 MONITOR WELL DRILLING\PROJECT DATA\GINT\GINT FILES\CI WELLS.GPJ

HALEY ALDRICH		LITHOLOGIC LOG				M56-LBF	
Project     Production Test Facility						Cadastral Location	
Client     Florence Copper, Inc.						D (4-9) 28 CBD	
Contractor   National EWP, Inc.							
Drilling Method     Conventional Mud Rotary		Concrete Pad     1477.32     feet, amsl		Start     April 13, 2017			
Borehole Diameter(s)   10.625		Datum     State Plane NAD 83		Finish     April 14, 2017			
Rig Make & Model     Schramm T685WS		Location     N 746,317     E 847,592		H&A Rep.     C. Price			
Elevation (ft)	Depth (ft)	Well Diagram	USCS Symbol	Stratum Change Depth (ft)	LITHOLOGY IDENTIFICATION AND DESCRIPTION	COMMENTS	
0  1460  1440  1420  1400  1380  1360  1340  1320  1300  1280  1260  1240  1220  1200  1180  1160  1140	0		SP		<b>POORLY GRADED SAND (0-20 feet)</b> Primarily fine to coarse sand with ~5% fines and ~5% gravel to 10 mm. Sand is subrounded, gravel is subangular. Fines are nonplastic, are dark brown (7.5YR 3/4), and there is a weak reaction to HCL. <b>UBFU</b>	<b>Well Registry ID:</b> 55-226795 <b>Surface Completion:</b> Locking Well Vault & Concrete Pad <b>Well casing stickup:</b> 1.8 feet als <b>COLOR IDENTIFICATION MADE WITH WET SAMPLES USING MUNSELL CHART</b>  <b>Surface Casing:</b> 14-inch mild steel; 0 - 40 feet <b>Well Casing:</b> Nominal 5-inch diameter Mild Steel; 0 - 320 feet  <b>Unit Intervals:</b> UBFU: 0 - 282 feet MGFU: 282 - 302 feet LBFU: 302 - 352 feet  <b>Seal:</b> Type V neat cement; 0 - 297 feet Fine Sand & Bentonite; 297 - 310 feet	
	20		GP-GM	20	<b>POORLY GRADED GRAVEL with SAND and SILT (20-40 feet)</b> Composition roughly equal parts sand and gravel to 6 mm with ~10% fines. Sand and gravel is subangular. Fines have low plasticity, are very dark grey (7.5 YR 3/1), and have a weak reaction to HCL. <b>UBFU</b>		
	40		SP-SM	40	<b>POORLY GRADED SAND with SILT (40-70 feet)</b> Primarily fine to medium sand with ~10% fines and ~5% gravel to 6 mm. Sand is subrounded, gravel is rounded. Fines have low plasticity, are brown (7.5YR 4/2), and have a weak reaction to HCL. <b>UBFU</b>		
	60		SP-SC	70	<b>POORLY GRADED SAND with CLAY (70-120 feet)</b> Primarily fine to medium sand with ~10% fines and ~10% gravel to 12 mm. Sand and gravel is subangular. Fines have medium plasticity, are brown (7.5YR 4/2), and have no reaction to HCL. <b>UBFU</b>		
	80						
	100		CL	120	<b>SANDY LEAN CLAY (120-150 feet)</b> Primarily fines with ~30% sands and trace gravel to 6 mm. Sand is subrounded, gravel is angular. Fines have medium plasticity, medium toughness, slow dilatancy, high dry strength, are brown (7.5YR 4/4), and have a weak reaction to HCL. <b>UBFU</b>		
	120						
	140						
	160		SC	150	<b>CLAYEY SAND (150-180 feet)</b> Primarily fine to medium sand with ~40% fines and ~5% gravel to 12 mm. Sand is subangular, gravel is subrounded. Fines have medium plasticity, low toughness, are reddish brown (5YR 5/3), and have a weak reaction to HCL. <b>UBFU</b>		
	180		SP	180	<b>POORLY GRADED SAND with GRAVEL (180-282 feet)</b> Primarily medium to coarse sand with ~5% fines and ~25% gravel to 12 mm. Sand and gravel is subangular. Fines are nonplastic, are reddish brown (5YR 4/4), and there is a medium reaction to HCL. <b>UBFU</b> Depth interval adjusted to reflect e-log for MFGU.		
	200						
	220		CH	282	<b>FAT CLAY with SAND (282-302 feet)</b> Primarily fines with ~20% sand to <2 mm. Sand is subrounded. Fines have high plasticity, high toughness, slow dilatancy, high dry strength, are reddish brown (5YR 4/3), and have a medium reaction to HCL. <b>MFGU</b> Depth interval adjusted to reflect e-log for MFGU.		
240							
260							
280	SW	302	<b>WELL GRADED SAND with GRAVEL (302-352 feet)</b> Primarily fine to coarse sand with ~5% fines and ~20% gravel to 10 mm. Sand and gravel is angular. The color is reddish brown (5YR 5/4), and there is a strong reaction to HCL. <b>LBFU</b> Depth interval adjusted to reflect e-log for MFGU.				
300							
320		352			<b>Total Depth:</b> Driller Depth = 352 feet; Geophysical Logging Depth = 352 feet		
NOTE: Lithologic descriptions, group symbols, and grain-size determinations based on the USCS visual-manual method (Haley & Aldrich OP2001A - Field Practice for Soil Identification and Description).							
						Sheet No. 1    of    1	



## **APPENDIX C**

### **Chemical Characterization of Formation Water**



May 23, 2018

Barbara Sylvester  
Brown & Caldwell  
201 E. Washington Suite 500  
Phoenix, AZ 85004

TEL (602) 567-3894  
FAX -

Work Order No.: 18D0619  
Order Name: Florence Copper

RE: PTF

Dear Barbara Sylvester,

Turner Laboratories, Inc. received 2 sample(s) on 04/25/2018 for the analyses presented in the following report.

All results are intended to be considered in their entirety, and Turner Laboratories, Inc. is not responsible for use of less than the complete report. Results apply only to the samples analyzed. Samples will be disposed of 30 days after issue of our report unless special arrangements are made.

The pages that follow may contain sensitive, privileged or confidential information intended solely for the addressee named above. If you receive this message and are not the agent or employee of the addressee, this communication has been sent in error. Please do not disseminate or copy any of the attached and notify the sender immediately by telephone. Please also return the attached sheet(s) to the sender by mail.

Please call if you have any questions.

Respectfully submitted,

Turner Laboratories, Inc.  
ADHS License AZ0066

Kevin Brim  
Project Manager

Client: Brown & Caldwell  
Project: PTF  
Work Order: 18D0619  
Date Received: 04/25/2018

Order: Florence Copper

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Matrix	Collection Date/Time
18D0619-01	R-09	Ground Water	04/23/2018 1555
18D0619-02	TB	Ground Water	04/25/2018 0000

**Client:** Brown & Caldwell  
**Project:** PTF  
**Work Order:** 18D0619  
**Date Received:** 04/25/2018

**Case Narrative**

---

The 8015D analysis was performed by TestAmerica Laboratories, Inc. in Phoenix, AZ.

The radiochemistry analysis was performed by Radiation Safety Engineering, Inc. in Chandler, AZ.

D5 Minimum Reporting Limit (MRL) is adjusted due to sample dilution; analyte was non-detect in the sample.

H5 This test is specified to be performed in the field within 15 minutes of sampling; sample was received and analyzed past the regulatory holding time.

M3 The spike recovery value is unusable since the analyte concentration in the sample is disproportionate to the spike level. The associated LCS/LCSD recovery was acceptable.

All soil, sludge, and solid matrix determinations are reported on a wet weight basis unless otherwise noted.

ND Not Detected at or above the PQL

PQL Practical Quantitation Limit

DF Dilution Factor

PRL Project Reporting Limit



Client: Brown & Caldwell

Project: PTF

Work Order: 18D0619

Lab Sample ID: 18D0619-01

Client Sample ID: R-09

Collection Date/Time: 04/23/2018 1555

Matrix: Ground Water

Order Name: Florence Copper

Analyses	Result	PRL	PQL	Qual	Units	DF	Prep Date	Analysis Date	Analyst
ICP Dissolved Metals-E 200.7 (4.4)									
Calcium	140		4.0	M3	mg/L	1	04/27/2018 1440	05/04/2018 1150	MH
Iron	ND		0.30		mg/L	1	04/27/2018 1440	05/04/2018 1150	MH
Magnesium	27		3.0		mg/L	1	04/27/2018 1440	05/04/2018 1150	MH
Potassium	6.8		5.0		mg/L	1	04/27/2018 1440	05/04/2018 1150	MH
Sodium	170		5.0	M3	mg/L	1	04/27/2018 1440	05/04/2018 1150	MH
ICP/MS Dissolved Metals-E 200.8 (5.4)									
Aluminum	ND		0.0800	D5	mg/L	2	04/27/2018 1440	05/07/2018 1139	MH
Antimony	ND		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Arsenic	0.0016		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Barium	0.071		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Beryllium	ND		0.00050	D5	mg/L	2	04/27/2018 1440	05/07/2018 1139	MH
Cadmium	ND		0.00025		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Chromium	0.0051		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Cobalt	ND		0.00025		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Copper	0.011		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Lead	ND		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Manganese	0.0020		0.00025		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Nickel	0.0033		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Selenium	ND		0.0025		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Thallium	ND		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Zinc	ND		0.040		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
CVAA Dissolved Mercury-E 245.1									
Mercury	ND		0.0010		mg/L	1	04/26/2018 0955	04/26/2018 1639	MH
pH-E150.1									
pH (pH Units)	7.8			H5	-	1	04/26/2018 1615	04/26/2018 1616	AP
Temperature (°C)	22			H5	-	1	04/26/2018 1615	04/26/2018 1616	AP
ICP/MS Total Metals-E200.8 (5.4)									
Uranium	0.016		0.00050		mg/L	1	04/27/2018 1230	04/30/2018 1348	MH

Client: Brown & Caldwell

Project: PTF

Work Order: 18D0619

Lab Sample ID: 18D0619-01

Client Sample ID: R-09

Collection Date/Time: 04/23/2018 1555

Matrix: Ground Water

Order Name: Florence Copper

Analyses	Result	PRL	PQL	Qual	Units	DF	Prep Date	Analysis Date	Analyst
Anions by Ion Chromatography-E300.0 (2.1)									
Chloride	310		25		mg/L	25	04/26/2018 1225	04/26/2018 1415	AP
Fluoride	ND		0.50		mg/L	1	04/25/2018 1208	04/25/2018 1544	AP
Nitrogen, Nitrate (As N)	8.8		0.50		mg/L	1	04/25/2018 1208	04/25/2018 1544	AP
Nitrogen, Nitrite (As N)	ND		0.10		mg/L	1	04/25/2018 1208	04/25/2018 1544	AP
Sulfate	190		130		mg/L	25	04/26/2018 1225	04/26/2018 1415	AP
Cyanide-E335.4									
Cyanide	ND		0.10		mg/L	1	04/26/2018 0845	04/30/2018 1545	AP
Alkalinity-SM2320B									
Alkalinity, Bicarbonate (As CaCO3)	150		2.0		mg/L	1	05/03/2018 1030	05/03/2018 1210	EJ
Alkalinity, Carbonate (As CaCO3)	ND		2.0		mg/L	1	05/03/2018 1030	05/03/2018 1210	EJ
Alkalinity, Hydroxide (As CaCO3)	ND		2.0		mg/L	1	05/03/2018 1030	05/03/2018 1210	EJ
Alkalinity, Phenolphthalein (As CaCO3)	ND		2.0		mg/L	1	05/03/2018 1030	05/03/2018 1210	EJ
Alkalinity, Total (As CaCO3)	150		2.0		mg/L	1	05/03/2018 1030	05/03/2018 1210	EJ
Specific Conductance-SM2510 B									
Conductivity	1700		0.20		µmhos/cm	2	05/09/2018 1315	05/09/2018 1330	AP
Total Dissolved Solids (Residue, Filterable)-SM2540 C									
Total Dissolved Solids (Residue, Filterable)	1000		20		mg/L	1	04/26/2018 0826	05/01/2018 1600	EJ
Volatile Organic Compounds by GC/MS-SW8260B									
Benzene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 1943	KP
Carbon disulfide	ND		2.0		ug/L	1	05/07/2018 1824	05/07/2018 1943	KP
Ethylbenzene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 1943	KP
Toluene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 1943	KP
Xylenes, Total	ND		1.5		ug/L	1	05/07/2018 1824	05/07/2018 1943	KP
Surr: 4-Bromofluorobenzene	95	70-130			%REC	1	05/07/2018 1824	05/07/2018 1943	KP
Surr: Dibromofluoromethane	101	70-130			%REC	1	05/07/2018 1824	05/07/2018 1943	KP
Surr: Toluene-d8	77	70-130			%REC	1	05/07/2018 1824	05/07/2018 1943	KP

Client:

Project:

Work Order:

Lab Sample ID:

Brown & Caldwell  
PTF  
18D0619  
18D0619-02

Client Sample ID: TB

Collection Date/Time: 04/25/2018 0000

Matrix: Ground Water

Order Name: Florence Copper

Analyses	Result	PRL	PQL	Qual	Units	DF	Prep Date	Analysis Date	Analyst
Volatile Organic Compounds by GC/MS-SW8260B									
Benzene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 2344	KP
Carbon disulfide	ND		2.0		ug/L	1	05/07/2018 1824	05/07/2018 2344	KP
Ethylbenzene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 2344	KP
Toluene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 2344	KP
Xylenes, Total	ND		1.5		ug/L	1	05/07/2018 1824	05/07/2018 2344	KP
Surr: 4-Bromofluorobenzene	101	70-130			%REC	1	05/07/2018 1824	05/07/2018 2344	KP
Surr: Dibromofluoromethane	110	70-130			%REC	1	05/07/2018 1824	05/07/2018 2344	KP
Surr: Toluene-d8	103	70-130			%REC	1	05/07/2018 1824	05/07/2018 2344	KP

Client: Brown & Caldwell  
Project: PTF  
Work Order: 18D0619  
Date Received: 04/25/2018

QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1804269 - E 245.1										
Blank (1804269-BLK1)				Prepared & Analyzed: 04/26/2018						
Mercury	ND	0.0010	mg/L							
LCS (1804269-BS1)				Prepared & Analyzed: 04/26/2018						
Mercury	0.0049	0.0010	mg/L	0.005000		98	85-115			
LCS Dup (1804269-BSD1)				Prepared & Analyzed: 04/26/2018						
Mercury	0.0048	0.0010	mg/L	0.005000		95	85-115	2	20	
Matrix Spike (1804269-MS1)				Source: 18D0394-01			Prepared & Analyzed: 04/26/2018			
Mercury	0.0050	0.0010	mg/L	0.005000	0.00020	97	85-115			
Matrix Spike Dup (1804269-MSD1)				Source: 18D0394-01			Prepared & Analyzed: 04/26/2018			
Mercury	0.0050	0.0010	mg/L	0.005000	0.00020	96	85-115	1	20	
Batch 1804292 - E200.8 (5.4)										
Blank (1804292-BLK1)				Prepared & Analyzed: 04/30/2018						
Uranium	ND	0.00050	mg/L							
LCS (1804292-BS1)				Prepared & Analyzed: 04/30/2018						
Uranium	0.046	0.00050	mg/L	0.05000		92	85-115			
LCS Dup (1804292-BSD1)				Prepared & Analyzed: 04/30/2018						
Uranium	0.046	0.00050	mg/L	0.05000		92	85-115	0.2	20	
Matrix Spike (1804292-MS1)				Source: 18D0614-01			Prepared & Analyzed: 04/30/2018			
Uranium	0.051	0.00050	mg/L	0.05000	0.0015	99	70-130			
Batch 1805051 - E 200.7 (4.4)										
Blank (1805051-BLK1)				Prepared & Analyzed: 05/04/2018						
Calcium	ND	4.0	mg/L							
Iron	ND	0.30	mg/L							
Magnesium	ND	3.0	mg/L							
Potassium	ND	5.0	mg/L							
Sodium	ND	5.0	mg/L							
LCS (1805051-BS1)				Prepared & Analyzed: 05/04/2018						
Calcium	11	4.0	mg/L	10.00		109	85-115			
Iron	1.0	0.30	mg/L	1.000		104	85-115			
Magnesium	10	3.0	mg/L	10.00		105	85-115			
Potassium	10	5.0	mg/L	10.00		105	85-115			
Sodium	10	5.0	mg/L	10.00		105	85-115			
LCS Dup (1805051-BSD1)				Prepared & Analyzed: 05/04/2018						
Calcium	11	4.0	mg/L	10.00		110	85-115	1	20	
Iron	1.0	0.30	mg/L	1.000		105	85-115	0.5	20	
Magnesium	10	3.0	mg/L	10.00		105	85-115	0.06	20	
Potassium	10	5.0	mg/L	10.00		105	85-115	0.05	20	
Sodium	11	5.0	mg/L	10.00		109	85-115	4	20	

Client: Brown & Caldwell  
Project: PTF  
Work Order: 18D0619  
Date Received: 04/25/2018

QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1805051 - E 200.7 (4.4)										
Matrix Spike (1805051-MS1)		Source: 18D0619-01		Prepared & Analyzed: 05/04/2018						
Calcium	150	4.0	mg/L	10.00	140	59	70-130			M3
Iron	1.1	0.30	mg/L	1.000	0.028	105	70-130			
Magnesium	38	3.0	mg/L	10.00	27	108	70-130			
Potassium	17	5.0	mg/L	10.00	6.8	105	70-130			
Sodium	170	5.0	mg/L	10.00	170	30	70-130			M3
Matrix Spike (1805051-MS2)		Source: 18E0021-01		Prepared & Analyzed: 05/04/2018						
Calcium	64	4.0	mg/L	10.00	54	103	70-130			
Iron	1.0	0.30	mg/L	1.000	0.0060	101	70-130			
Magnesium	21	3.0	mg/L	10.00	11	99	70-130			
Potassium	15	5.0	mg/L	10.00	4.7	104	70-130			
Sodium	99	5.0	mg/L	10.00	90	87	70-130			
Batch 1805069 - E 200.8 (5.4)										
Blank (1805069-BLK1)		Prepared & Analyzed: 05/07/2018								
Aluminum	ND	0.0400	mg/L							
Antimony	ND	0.00050	mg/L							
Arsenic	ND	0.00050	mg/L							
Barium	ND	0.00050	mg/L							
Beryllium	ND	0.00025	mg/L							
Cadmium	ND	0.00025	mg/L							
Chromium	ND	0.00050	mg/L							
Cobalt	ND	0.00025	mg/L							
Copper	ND	0.00050	mg/L							
Lead	ND	0.00050	mg/L							
Manganese	ND	0.00025	mg/L							
Nickel	ND	0.00050	mg/L							
Selenium	ND	0.0025	mg/L							
Thallium	ND	0.00050	mg/L							
Zinc	ND	0.040	mg/L							
LCS (1805069-BS1)		Prepared & Analyzed: 05/07/2018								
Aluminum	0.104	0.0400	mg/L	0.1000		104	85-115			
Antimony	0.048	0.00050	mg/L	0.05000		96	85-115			
Arsenic	0.050	0.00050	mg/L	0.05000		100	85-115			
Barium	0.050	0.00050	mg/L	0.05000		100	85-115			
Beryllium	0.049	0.00025	mg/L	0.05000		97	85-115			
Cadmium	0.050	0.00025	mg/L	0.05000		100	85-115			
Chromium	0.051	0.00050	mg/L	0.05000		102	85-115			
Cobalt	0.051	0.00025	mg/L	0.05000		101	85-115			
Copper	0.051	0.00050	mg/L	0.05000		103	85-115			
Lead	0.049	0.00050	mg/L	0.05000		98	85-115			
Manganese	0.050	0.00025	mg/L	0.05000		101	85-115			
Nickel	0.051	0.00050	mg/L	0.05000		102	85-115			
Selenium	0.051	0.0025	mg/L	0.05000		103	85-115			
Thallium	0.050	0.00050	mg/L	0.05000		101	85-115			
Zinc	0.10	0.040	mg/L	0.1000		101	85-115			



Client: Brown & Caldwell  
Project: PTF  
Work Order: 18D0619  
Date Received: 04/25/2018

QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1805069 - E 200.8 (5.4)										
LCS Dup (1805069-BSD1)				Prepared & Analyzed: 05/07/2018						
Aluminum	0.115	0.0400	mg/L	0.1000		115	85-115	10	20	
Antimony	0.048	0.00050	mg/L	0.05000		96	85-115	0.7	20	
Arsenic	0.050	0.00050	mg/L	0.05000		101	85-115	0.8	20	
Barium	0.051	0.00050	mg/L	0.05000		102	85-115	1	20	
Beryllium	0.049	0.00025	mg/L	0.05000		97	85-115	0.2	20	
Cadmium	0.050	0.00025	mg/L	0.05000		100	85-115	0.2	20	
Chromium	0.051	0.00050	mg/L	0.05000		102	85-115	0.4	20	
Cobalt	0.050	0.00025	mg/L	0.05000		101	85-115	0.5	20	
Copper	0.052	0.00050	mg/L	0.05000		105	85-115	2	20	
Lead	0.049	0.00050	mg/L	0.05000		98	85-115	0.1	20	
Manganese	0.050	0.00025	mg/L	0.05000		101	85-115	0.09	20	
Nickel	0.051	0.00050	mg/L	0.05000		103	85-115	0.8	20	
Selenium	0.052	0.0025	mg/L	0.05000		104	85-115	2	20	
Thallium	0.050	0.00050	mg/L	0.05000		101	85-115	0.06	20	
Zinc	0.10	0.040	mg/L	0.1000		104	85-115	3	20	
Matrix Spike (1805069-MS1)				Source: 18D0693-01		Prepared & Analyzed: 05/07/2018				
Aluminum	0.239	0.0400	mg/L	0.1000	0.166	74	70-130			
Antimony	0.045	0.00050	mg/L	0.05000	0.00024	90	70-130			
Arsenic	0.056	0.00050	mg/L	0.05000	0.0035	104	70-130			
Barium	0.16	0.00050	mg/L	0.05000	0.12	94	70-130			
Beryllium	0.045	0.00025	mg/L	0.05000	0.000029	90	70-130			
Cadmium	0.047	0.00025	mg/L	0.05000	ND	94	70-130			
Chromium	0.049	0.00050	mg/L	0.05000	0.00052	98	70-130			
Cobalt	0.048	0.00025	mg/L	0.05000	0.00097	95	70-130			
Copper	0.051	0.00050	mg/L	0.05000	0.0020	98	70-130			
Lead	0.047	0.00050	mg/L	0.05000	0.00016	94	70-130			
Manganese	0.054	0.00025	mg/L	0.05000	0.0075	94	70-130			
Nickel	0.049	0.00050	mg/L	0.05000	0.0018	94	70-130			
Selenium	0.057	0.0025	mg/L	0.05000	ND	114	70-130			
Thallium	0.048	0.00050	mg/L	0.05000	0.000038	96	70-130			
Zinc	0.11	0.040	mg/L	0.1000	ND	109	70-130			

Client: Brown & Caldwell  
Project: PTF  
Work Order: 18D0619  
Date Received: 04/25/2018

QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1804261 - SM2540 C										
Duplicate (1804261-DUP1)		Source: 18D0606-01		Prepared: 04/26/2018 Analyzed: 04/27/2018						
Total Dissolved Solids (Residue, Filterable)	630	20	mg/L		630			0.3	5	
Duplicate (1804261-DUP2)		Source: 18D0606-02		Prepared: 04/26/2018 Analyzed: 04/27/2018						
Total Dissolved Solids (Residue, Filterable)	610	20	mg/L		620			0.8	5	
Batch 1804268 - E335.4										
Blank (1804268-BLK1)		Prepared: 04/26/2018 Analyzed: 04/30/2018								
Cyanide	ND	0.10	mg/L							
LCS (1804268-BS1)		Prepared: 04/26/2018 Analyzed: 04/30/2018								
Cyanide	2.0	0.10	mg/L	2.000		101	90-110			
LCS Dup (1804268-BSD1)		Prepared: 04/26/2018 Analyzed: 04/30/2018								
Cyanide	2.0	0.10	mg/L	2.000		101	90-110	0.1	20	
Matrix Spike (1804268-MS1)		Source: 18D0602-03		Prepared: 04/26/2018 Analyzed: 04/30/2018						
Cyanide	2.1	0.10	mg/L	2.000	ND	103	90-110			
Matrix Spike Dup (1804268-MSD1)		Source: 18D0602-03		Prepared: 04/26/2018 Analyzed: 04/30/2018						
Cyanide	2.0	0.10	mg/L	2.000	ND	98	90-110	5	20	
Batch 1804272 - E150.1										
Duplicate (1804272-DUP1)		Source: 18D0662-02		Prepared & Analyzed: 04/26/2018						
pH (pH Units)	7.8		-		7.8			0.1	200	H5
Temperature (°C)	21		-		21			2	200	H5
Batch 1805027 - SM2320B										
LCS (1805027-BS1)		Prepared & Analyzed: 05/03/2018								
Alkalinity, Total (As CaCO3)	240	2.0	mg/L	250.0		96	90-110			
LCS Dup (1805027-BSD1)		Prepared & Analyzed: 05/03/2018								
Alkalinity, Total (As CaCO3)	240	2.0	mg/L	250.0		96	90-110	0	10	
Matrix Spike (1805027-MS1)		Source: 18D0606-02		Prepared & Analyzed: 05/03/2018						
Alkalinity, Total (As CaCO3)	370	2.0	mg/L	250.0	130	96	85-115			
Matrix Spike Dup (1805027-MSD1)		Source: 18D0606-02		Prepared & Analyzed: 05/03/2018						
Alkalinity, Total (As CaCO3)	370	2.0	mg/L	250.0	130	95	85-115	0.5	10	
Batch 1805103 - SM2510 B										
LCS (1805103-BS1)		Prepared & Analyzed: 05/09/2018								
Conductivity	140	0.10	µmhos/cm	141.2		101	0-200			
LCS Dup (1805103-BSD1)		Prepared & Analyzed: 05/09/2018								
Conductivity	140	0.10	µmhos/cm	141.2		101	0-200	0.7	200	
Duplicate (1805103-DUP1)		Source: 18E0192-01		Prepared & Analyzed: 05/09/2018						
Conductivity	4.0	0.10	µmhos/cm		4.0			0	10	

Client: Brown & Caldwell  
Project: PTF  
Work Order: 18D0619  
Date Received: 04/25/2018


QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1805074 - SW8260B										
Blank (1805074-BLK1)				Prepared & Analyzed: 05/07/2018						
Benzene	ND	0.50	ug/L							
Carbon disulfide	ND	2.0	ug/L							
Ethylbenzene	ND	0.50	ug/L							
Toluene	ND	0.50	ug/L							
Xylenes, Total	ND	1.5	ug/L							
Surrogate: 4-Bromofluorobenzene	25.0		ug/L	25.00		100	70-130			
Surrogate: Dibromofluoromethane	26.9		ug/L	25.00		107	70-130			
Surrogate: Toluene-d8	25.1		ug/L	25.00		100	70-130			
LCS (1805074-BS1)				Prepared & Analyzed: 05/07/2018						
1,1-Dichloroethene	29		ug/L	25.00		114	70-130			
Benzene	27		ug/L	25.00		109	70-130			
Chlorobenzene	29		ug/L	25.00		115	70-130			
Toluene	25		ug/L	25.00		101	70-130			
Trichloroethene	26		ug/L	25.00		103	70-130			
Surrogate: 4-Bromofluorobenzene	24.6		ug/L	25.00		98	70-130			
Surrogate: Dibromofluoromethane	25.6		ug/L	25.00		102	70-130			
Surrogate: Toluene-d8	24.8		ug/L	25.00		99	70-130			
LCS Dup (1805074-BSD1)				Prepared & Analyzed: 05/07/2018						
1,1-Dichloroethene	27		ug/L	25.00		110	70-130	4	30	
Benzene	26		ug/L	25.00		104	70-130	5	30	
Chlorobenzene	26		ug/L	25.00		105	70-130	9	30	
Toluene	24		ug/L	25.00		96	70-130	5	30	
Trichloroethene	25		ug/L	25.00		98	70-130	4	30	
Surrogate: 4-Bromofluorobenzene	24.4		ug/L	25.00		98	70-130			
Surrogate: Dibromofluoromethane	26.1		ug/L	25.00		104	70-130			
Surrogate: Toluene-d8	25.1		ug/L	25.00		100	70-130			
Matrix Spike (1805074-MS1)		Source: 18D0582-02		Prepared & Analyzed: 05/07/2018						
1,1-Dichloroethene	27		ug/L	25.00	0.070	109	70-130			
Benzene	26		ug/L	25.00	0.020	104	70-130			
Chlorobenzene	26		ug/L	25.00	0.0	105	70-130			
Toluene	27		ug/L	25.00	3.5	95	70-130			
Trichloroethene	24		ug/L	25.00	0.040	97	70-130			
Surrogate: 4-Bromofluorobenzene	24.4		ug/L	25.00		98	70-130			
Surrogate: Dibromofluoromethane	26.4		ug/L	25.00		106	70-130			
Surrogate: Toluene-d8	24.9		ug/L	25.00		100	70-130			
Matrix Spike Dup (1805074-MSD1)		Source: 18D0582-02		Prepared & Analyzed: 05/07/2018						
1,1-Dichloroethene	27		ug/L	25.00	0.070	108	70-130	0.8	30	
Benzene	25		ug/L	25.00	0.020	101	70-130	2	30	
Chlorobenzene	26		ug/L	25.00	0.0	105	70-130	0.3	30	
Toluene	27		ug/L	25.00	3.5	95	70-130	0.1	30	
Trichloroethene	24		ug/L	25.00	0.040	95	70-130	2	30	
Surrogate: 4-Bromofluorobenzene	24.7		ug/L	25.00		99	70-130			
Surrogate: Dibromofluoromethane	26.4		ug/L	25.00		106	70-130			
Surrogate: Toluene-d8	25.3		ug/L	25.00		101	70-130			

Client: Brown & Caldwell  
Project: PTF  
Work Order: 18D0619  
Date Received: 04/25/2018

QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1804245 - E300.0 (2.1)										
Blank (1804245-BLK1)				Prepared & Analyzed: 04/25/2018						
Chloride	ND	1.0	mg/L							
Fluoride	ND	0.50	mg/L							
Nitrogen, Nitrate (As N)	ND	0.50	mg/L							
Nitrogen, Nitrite (As N)	ND	0.10	mg/L							
Sulfate	ND	5.0	mg/L							
LCS (1804245-BS1)				Prepared & Analyzed: 04/25/2018						
Chloride	12	1.0	mg/L	12.50		92	90-110			
Fluoride	2.0	0.50	mg/L	2.000		101	90-110			
Nitrogen, Nitrate (As N)	4.7	0.50	mg/L	5.000		95	90-110			
Nitrogen, Nitrite (As N)	2.3	0.10	mg/L	2.500		92	90-110			
Sulfate	12	5.0	mg/L	12.50		96	90-110			
LCS Dup (1804245-BSD1)				Prepared & Analyzed: 04/25/2018						
Chloride	12	1.0	mg/L	12.50		94	90-110	2	10	
Fluoride	2.0	0.50	mg/L	2.000		101	90-110	0.4	10	
Nitrogen, Nitrate (As N)	4.9	0.50	mg/L	5.000		98	90-110	3	10	
Nitrogen, Nitrite (As N)	2.4	0.10	mg/L	2.500		95	90-110	3	10	
Sulfate	12	5.0	mg/L	12.50		98	90-110	3	10	
Matrix Spike (1804245-MS1)		Source: 18D0613-08		Prepared & Analyzed: 04/25/2018						
Fluoride	3.7	0.50	mg/L	2.000	1.7	100	80-120			
Nitrogen, Nitrate (As N)	4.7	0.50	mg/L	5.000	0.22	89	80-120			
Matrix Spike (1804245-MS2)		Source: 18D0625-01		Prepared & Analyzed: 04/26/2018						
Nitrogen, Nitrate (As N)	5.0	0.50	mg/L	5.000	0.46	92	80-120			
Nitrogen, Nitrite (As N)	2.2	0.10	mg/L	2.500	ND	88	80-120			
Matrix Spike (1804245-MS3)		Source: 18D0614-01RE1		Prepared & Analyzed: 04/26/2018						
Chloride	17		mg/L	12.50	6.4	88	80-120			
Sulfate	28		mg/L	12.50	18	85	80-120			
Matrix Spike Dup (1804245-MSD1)		Source: 18D0613-08		Prepared & Analyzed: 04/25/2018						
Fluoride	3.7	0.50	mg/L	2.000	1.7	100	80-120	0.4	10	
Nitrogen, Nitrate (As N)	4.7	0.50	mg/L	5.000	0.22	90	80-120	0.6	10	
Matrix Spike Dup (1804245-MSD2)		Source: 18D0625-01		Prepared & Analyzed: 04/26/2018						
Nitrogen, Nitrate (As N)	5.1	0.50	mg/L	5.000	0.46	92	80-120	0.2	10	
Nitrogen, Nitrite (As N)	2.2	0.10	mg/L	2.500	ND	88	80-120	0.4	10	
Matrix Spike Dup (1804245-MSD3)		Source: 18D0614-01RE1		Prepared & Analyzed: 04/26/2018						
Chloride	18		mg/L	12.50	6.4	89	80-120	0.6	10	
Sulfate	29		mg/L	12.50	18	86	80-120	0.6	10	



TURNER WORK ORDER # 18D0619 DATE 4/23/18 PAGE 1 OF 1

Page 13 of 32

## ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Phoenix

4625 East Cotton Ctr Blvd

Suite 189

Phoenix, AZ 85040

Tel: (602)437-3340

TestAmerica Job ID: 550-101943-1

Client Project/Site: 18D0619

For:

Turner Laboratories, Inc.

2445 North Coyote Drive

Suite 104

Tucson, Arizona 85745

Attn: Kevin Brim



Authorized for release by:

5/16/2018 12:23:25 PM

Ken Baker, Project Manager II

(602)659-7624

[ken.baker@testamericainc.com](mailto:ken.baker@testamericainc.com)

### LINKS

Review your project  
results through

TotalAccess

Have a Question?



Visit us at:

[www.testamericainc.com](http://www.testamericainc.com)

*This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.*

*Results relate only to the items tested and the sample(s) as received by the laboratory.*



# Table of Contents

Cover Page . . . . .	1
Table of Contents . . . . .	2
Definitions/Glossary . . . . .	3
Case Narrative . . . . .	4
Sample Summary . . . . .	5
Detection Summary . . . . .	6
Client Sample Results . . . . .	7
Surrogate Summary . . . . .	8
QC Sample Results . . . . .	9
QC Association Summary . . . . .	10
Lab Chronicle . . . . .	11
Certification Summary . . . . .	12
Method Summary . . . . .	13
Chain of Custody . . . . .	14
Receipt Checklists . . . . .	15



## Definitions/Glossary

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

### Qualifiers

#### GC Semi VOA

Qualifier	Qualifier Description
Q9	Insufficient sample received to meet method QC requirements.

### Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

# Case Narrative

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

**Job ID: 550-101943-1**

**Laboratory: TestAmerica Phoenix**

## Narrative

**Job Narrative**  
**550-101943-1**

### Comments

No additional comments.

### Receipt

The sample was received on 4/27/2018 10:50 AM; the sample arrived in good condition, properly preserved and, where required, on ice. The temperature of the cooler at receipt was 3.8° C.

### GC Semi VOA

Method(s) 8015D: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate/sample duplicate (MS/MSD) associated with preparation batch 550-145985 and analytical batch 550-146884. Affected samples have been added a Q9 qualifier. 18D0619-01 (550-101943-1)

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

### Organic Prep

Method(s) 3510C: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate (MS/MSD) associated with 3510C.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

# Sample Summary

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
550-101943-1	18D0619-01	Water	04/23/18 15:55	04/27/18 10:50

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

Detection Summary

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Client Sample ID: 18D0619-01      Lab Sample ID: 550-101943-1

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
ORO (C22-C32)	0.21	Q9	0.20	mg/L	1		8015D	Total/NA

This Detection Summary does not include radiochemical test results.



# Client Sample Results

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Client Sample ID: 18D0619-01

Date Collected: 04/23/18 15:55

Date Received: 04/27/18 10:50

Lab Sample ID: 550-101943-1

Matrix: Water

## Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
ORO (C22-C32)	0.21	Q9	0.20	mg/L		04/30/18 14:16	05/10/18 23:29	1
DRO (C10-C22)	ND	Q9	0.10	mg/L		04/30/18 14:16	05/10/18 23:29	1
Surrogate	%Recovery	Qualifier	Limits			Prepared	Analyzed	Dil Fac
o-Terphenyl (Surr)	79		10 - 150			04/30/18 14:16	05/10/18 23:29	1

# Surrogate Summary

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Method: 8015D - Diesel Range Organics (DRO) (GC)

Matrix: Water

Prep Type: Total/NA

Percent Surrogate Recovery (Acceptance Limits)		
Lab Sample ID	Client Sample ID	OTPH (10-150)
550-101943-1	18D0619-01	79
LCS 550-145985/2-A	Lab Control Sample	79
LCSD 550-145985/3-A	Lab Control Sample Dup	79
MB 550-145985/1-A	Method Blank	65
<b>Surrogate Legend</b>		
OTPH = o-Terphenyl (Surr)		

# QC Sample Results

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

## Method: 8015D - Diesel Range Organics (DRO) (GC)

Lab Sample ID: MB 550-145985/1-A

Matrix: Water

Analysis Batch: 146884

Client Sample ID: Method Blank

Prep Type: Total/NA

Prep Batch: 145985

Analyte	MB Result	MB Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
ORO (C22-C32)	ND		0.20	mg/L		04/30/18 14:15	05/11/18 11:16	1
DRO (C10-C22)	ND		0.10	mg/L		04/30/18 14:15	05/11/18 11:16	1
Surrogate	MB %Recovery	MB Qualifier	Limits			Prepared	Analyzed	Dil Fac
o-Terphenyl (Surr)	65		10 - 150			04/30/18 14:15	05/11/18 11:16	1

Lab Sample ID: LCS 550-145985/2-A

Matrix: Water

Analysis Batch: 146884

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Prep Batch: 145985

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
ORO (C22-C32)	1.60	1.59		mg/L		99	69 - 107
DRO (C10-C22)	0.400	0.450		mg/L		113	42 - 133
Surrogate	LCS %Recovery	LCS Qualifier	Limits				
o-Terphenyl (Surr)	79		10 - 150				

Lab Sample ID: LCSD 550-145985/3-A

Matrix: Water

Analysis Batch: 146884

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Prep Batch: 145985

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
ORO (C22-C32)	1.60	1.59		mg/L		100	69 - 107	0	20
DRO (C10-C22)	0.400	0.447		mg/L		112	42 - 133	1	22
Surrogate	LCSD %Recovery	LCSD Qualifier	Limits						
o-Terphenyl (Surr)	79		10 - 150						

TestAmerica Phoenix

## QC Association Summary

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

### GC Semi VOA

#### Prep Batch: 145985

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
550-101943-1	18D0619-01	Total/NA	Water	3510C	
MB 550-145985/1-A	Method Blank	Total/NA	Water	3510C	
LCS 550-145985/2-A	Lab Control Sample	Total/NA	Water	3510C	
LCSD 550-145985/3-A	Lab Control Sample Dup	Total/NA	Water	3510C	

#### Analysis Batch: 146884

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
550-101943-1	18D0619-01	Total/NA	Water	8015D	145985
MB 550-145985/1-A	Method Blank	Total/NA	Water	8015D	145985
LCS 550-145985/2-A	Lab Control Sample	Total/NA	Water	8015D	145985
LCSD 550-145985/3-A	Lab Control Sample Dup	Total/NA	Water	8015D	145985

# Lab Chronicle

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

**Client Sample ID: 18D0619-01**

**Date Collected: 04/23/18 15:55**

**Date Received: 04/27/18 10:50**

**Lab Sample ID: 550-101943-1**

**Matrix: Water**

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3510C			145985	04/30/18 14:16	REM	TAL PHX
Total/NA	Analysis	8015D		1	146884	05/10/18 23:29	TC1	TAL PHX

## Laboratory References:

TAL PHX = TestAmerica Phoenix, 4625 East Cotton Ctr Blvd, Suite 189, Phoenix, AZ 85040, TEL (602)437-3340



Accreditation/Certification Summary

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Laboratory: TestAmerica Phoenix

Unless otherwise noted, all analytes for this laboratory were covered under each accreditation/certification below.

Authority	Program	EPA Region	Identification Number	Expiration Date
Arizona	State Program	9	AZ0728	06-09-18
Analysis Method	Prep Method	Matrix	Analyte	

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

# Method Summary

Client: Turner Laboratories, Inc.  
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Method	Method Description	Protocol	Laboratory
8015D	Diesel Range Organics (DRO) (GC)	SW846	TAL PHX
3510C	Liquid-Liquid Extraction (Separatory Funnel)	SW846	TAL PHX

## Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

## Laboratory References:

TAL PHX = TestAmerica Phoenix, 4625 East Cotton Ctr Blvd, Suite 189, Phoenix, AZ 85040, TEL (602)437-3340

# SUBCONTRACT ORDER

Turner Laboratories, Inc.

18D0619

101943

## SENDING LABORATORY:

Turner Laboratories, Inc.  
2445 N. Coyote Drive, Ste #104  
Tucson, AZ 85745  
Phone: 520.882.5880  
Fax: 520.882.9788  
Project Manager: Kevin Brim

## RECEIVING LABORATORY:

TestAmerica Phoenix  
4625 East Cotton Center Boulevard Suite 189  
Phoenix, AZ 85540  
Phone : (602) 437-3340  
Fax:  
Please CC Kevin Brim Kbrim@turnerlabs.com

## Analysis

## Expires

## Laboratory ID

## Comments

Sample ID: 18D0619-01 Drinking Water Sampled: 04/23/2018 15:55

8015D Sub

04/30/2018 15:55

8015D DRO and ORO Paramaters Only

Containers Supplied:

## 8015D Sub

o-Terphenyl  
C10-C32 (Total)  
C22-C32 (Oil Range Organics)  
C10-C22 (Diesel Range Organics)  
C6-C10 (Gasoline Range Organics)

550-101943 Chain of Custody



TA-PHX

3.8 L  
LPS  
GVR

Released By

Date

Received By

Date

Released By

Date

Received By

Date

## Login Sample Receipt Checklist

Client: Turner Laboratories, Inc.

Job Number: 550-101943-1


**Login Number: 101943**

**List Source: TestAmerica Phoenix**

**List Number: 1**

**Creator: Gravlin, Andrea**

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	False	Check done at department level as required.



## Radiation Safety Engineering, Inc.

3245 N. WASHINGTON ST. • CHANDLER, ARIZONA 85225-1121

(480) 897-9459

Website: www.radsafe.com

FAX (480) 892-5446


### Radiochemical Activity in Water (pCi/L)

Turner Laboratories  
2445 N. Coyote Drive, Ste. 104  
Tucson, AZ 85745

Sampling Date: April 23, 2018  
Sample Received: May 01, 2018  
Analysis Completed: May 22, 2018

Sample ID	Gross Alpha Activity Method 600/00-02 (pCi/L)	Uranium Activity Method ASTM D6239 (pCi/L)	Adjusted Gross Alpha (pCi/L)	Radium 226 Activity Method GammaRay HPGE (pCi/L)	Radium 228 Activity Method GammaRay HPGE (pCi/L)	Total Radium (pCi/L)
18D0619-01	17.7 ± 0.9	12.9 ± 1.2	4.8 ± 1.5	3.1 ± 0.3	3.1 ± 0.4	6.2 ± 0.5

Date of Analysis	5/2/2018	5/21/2018	5/21/2018	5/4/2018	5/4/2018	5/4/2018
------------------	----------	-----------	-----------	----------	----------	----------

  
 Robert L. Metzger, Ph.D., C.H.P.      5/22/2018  
 Date  
 Laboratory License Number AZ0462





## Radiation Safety Engineering, Inc.

3245 N. WASHINGTON ST. • CHANDLER, ARIZONA 85225-1121

Website: [www.radsafe.com](http://www.radsafe.com)

(480) 897-9459

FAX (480) 892-5446

### Isotopic Uranium Analysis

Turner Laboratories  
2445 N. Coyote Drive, Ste. 104  
Tucson, AZ 85745

Sampling Date: April 23, 2018

Sample Received: May 01, 2018

Uranium Analysis Date: May 21, 2018

Sample No.	$^{238}\text{U}$	$^{235}\text{U}$	$^{234}\text{U}$	Total	
18D0619-01	$6.0 \pm 0.6$	$0.280 \pm 0.004$	$6.6 \pm 0.6$	$12.9 \pm 1.2$	Activity (pCi/L)
	$17.9 \pm 1.7$	$0.131 \pm 0.002$	$0.00106 \pm 0.00010$	$18.0 \pm 1.7$	Content ( $\mu\text{g/L}$ )
	Comments:				

*Robert L. Metzger*  
Robert L. Metzger, Ph.D., C.H.P.

5/22/2018

Date

Laboratory License Number AZ0462

Arizona Department of Environmental Quality  
**Drinking Water Radionuclides-Adjusted Gross Alpha, Radium 226 & 228, Uranium Analysis Report**  
 \*\*\*Samples To Be Taken At Entry Point Into Distribution System (EPDS) Only\*\*\*

PWS ID#: AZ04

PWS Name: \_\_\_\_\_

April 23, 2018 15:55 (24 hour clock)

Sample Date

Sample Time

Owner/Contact Person

Owner/Contact Fax Number

Owner/Contact Phone Number

Sample Collection Point

☐ EPDS # \_\_\_\_\_**Compliance Sample Type:**☐

Reduced Monitoring

Date Q1 collected: \_\_\_\_\_

☐

Quarterly

Date Q2 collected: \_\_\_\_\_

☐

Composite of four quarterly samples

Date Q3 collected: \_\_\_\_\_

Date Q4 collected: \_\_\_\_\_

**\*\*\*RADIOCHEMICAL ANALYSIS\*\*\***

&gt;&gt;&gt;To be filled out by laboratory personnel&lt;&lt;&lt;

**\*\*\*Combined Uranium must be reported in micrograms per liter\*\*\***

Analysis Method	MCL	Reporting Limit	Contaminant Name	Cont. Code	Analyses Run Date	Result	Exceed MCL
	15 pCi/L		Adjusted Gross Alpha	4000	5/21/2018	4.8 ± 1.5	
600/00-02		3 pCi/L	Gross Alpha	4002	5/2/2018	17.7 ± 0.9	
7500 - Rn			Radon	4004			
ASTM D6239	30 µg/L	1 µg/L	Combined Uranium	4006	5/21/2018	18.0 ± 1.7 µg/L	
			Uranium 234	4007	5/21/2018	0.00106 ± 0.00010	
			Uranium 235	4008	5/21/2018	0.131 ± 0.002	
			Uranium 238	4009	5/21/2018	17.9 ± 1.7	
	5 pCi/L	1 pCi/L	Combined Radium (226,228)	4010	5/4/2018	6.2 ± 0.5	X
GammaRay HPGE		1 pCi/L	Radium 226	4020	5/4/2018	3.1 ± 0.3	
GammaRay HPGE		1 pCi/L	Radium 228	4030	5/4/2018	3.1 ± 0.4	

**\*\*\*LABORATORY INFORMATION\*\*\***

&gt;&gt;&gt;To be filled out by laboratory personnel&lt;&lt;&lt;


Specimen Number: RSE60312

Lab ID Number: AZ0462

Lab Name: Radiation Safety Engineering, Inc.

Printed Name and Phone Number of Laboratory Contact: Robert L. Metzger, Ph.D., C.H.P. (480) 897-9459

Comments: 18D0619-01

Authorized Signature: 

Date Public Water System Notified: \_\_\_\_\_

DWAR 6: 11/2007

## SUBCONTRACT ORDER

Turner Laboratories, Inc.

18D0619

SENDING LABORATORY:

Turner Laboratories, Inc.  
2445 N. Coyote Drive, Ste #104  
Tucson, AZ 85745  
Phone: 520.882.5880  
Fax: 520.882.9788  
Project Manager: Kevin Brim

RECEIVING LABORATORY:

Radiation Safety Engineering, Inc.  
3245 N. Washington St.  
Chandler, AZ 85225-1121  
Phone : (480) 897-9459  
Fax: (480) 892-5446  
Please CC Kevin Brim Kbrim@turnerlabs.com

Analysis	Expires	Laboratory ID	Comments
<hr/>			
Sample ID: 18D0619-01 Drinking Water Sampled: 04/23/2018 15:55			
Radiochemistry, Gross Alpha	10/20/2018 15:55		Analyze Uranium and Adjusted Alpha if G. Alpha is > 12
Radiochemistry, Radium 226/228	05/23/2018 15:55		
Containers Supplied:			

H 60312

Released By

Date

4/30/18

16:00

ups

Received By

4/30/18

Date

16:00

Released By

Date

Received By

Date

## **APPENDIX D**

### **Well Completion Documentation**





## ESTIMATED ANNULAR MATERIAL RECORD

Project Name: FCI Project #: 129687-002 Date: 4-14-17  
Well No.: MSG-LBF Geologist: C Price

### ANNULAR VOLUME CALCULATIONS

Total Depth of Borehole [T]: <u>352</u> feet	Total Cased Depth: <u>340</u> feet
Borehole Diameter [D]: <u>10.625</u> inches	Rat Hole Volume [R=(D <sup>2</sup> ) 0.005454*L <sub>r</sub> ]: <u>7.4</u> Ft <sup>3</sup>
Screen Length [L <sub>s</sub> ]: <u>20</u> feet	Rat Hole Length [L <sub>r</sub> ]: <u>12</u> feet
Screen Diameter [d <sub>s</sub> ]: <u>5.63</u> inches	Camera Tube Length [L <sub>ct</sub> ]: <u>-</u> feet
Casing Length [L <sub>c</sub> ]: <u>320</u> feet	Camera Tube Diameter [d <sub>ct</sub> ]: <u>-</u> inches
Casing Diameter [d <sub>c</sub> ]: <u>5.63</u> inches	

Surface Casing 14" = 40' x 0.9 = 36 Ft<sup>3</sup>

Screen Annular Volume (A<sub>s</sub>): (D<sup>2</sup>-d<sub>s</sub><sup>2</sup>) 0.005454 = 0.44 Ft<sup>3</sup>/Lin. Ft  
Casing Annular Volume (A<sub>c</sub>): (D<sup>2</sup>-d<sub>c</sub><sup>2</sup>) 0.005454 = 0.44 Ft<sup>3</sup>/Lin. Ft  
Casing/Cam. Tube Annular Volume (A<sub>c+ct</sub>): (D<sup>2</sup>-d<sub>c</sub><sup>2</sup>-d<sub>ct</sub><sup>2</sup>) 0.005454 = - Ft<sup>3</sup>/Lin. Ft  
Tot Vol ≈ 175.4 Ft<sup>3</sup>

### EQUATIONS

2,700 lbs. Silica Sand = 1 cubic yard = 27 cubic feet

Bentonite Sack = 0.69 ft<sup>3</sup>


<sup>1</sup> Volume of bag (Ft<sup>3</sup>) = bag weight/100


Silica Sand Super Sack = 3000 lbs.

<sup>2</sup> Calculated depth = Previous Calculated depth - (v/A)

No.	✓	Weight of Bag (lbs.)	Volume of Bag <sup>1</sup> (v) (ft <sup>3</sup> )	Total Vol. of Bags (ft <sup>3</sup> )	Calculated Depth <sup>2</sup> (ft bls)	Tagged Depth (ft bls)	Comments
1	✓	1340	13.4	13.4	326.4	318	20- 5 gal 8x12 silica sand
2	✓	330	3.3	16.7	310.5	317	5- 5 gal 8x12 silica sand
3	✓	270	2.7	19.4	310.8	312	4- 5 gal 8x12 silica sand
						310	Swab - 16 min.
4	✓		4.5	23.9	299.7	297	1- 50 lb #60 silver sand w/
							6- 5 gal perl plug 1/4"
5	✓		189	212.9	-90	0	Cemex - 7.0 yards, 15.1 150/gal

Type V





Customer Code:	Customer Name:	Customer Job Number:	Order Code / Date:
318157	FLORENCE COPPER INC	FLORENCE WELL	G411 04/14/17
Project Code:	Project Name:	Project P.O. Number:	Order P.O. Number:
41097304	FLORENCE WELL	NO	NO
Ticket Date:	Delivery Address:	Map Page:	Map/Row/Column:
04/14/17	1575 W HUNT HIGHWAY	HAS D12 BATCH# AND JOE	PIN PINMYC01
Delivery Instructions:	TYPE II/V CEMENT HUNT HWY & E/ FELIX RD. MAX 7 YARD LOADS		Dispatcher:
			grslater
			Ticket Number:
			44095080

LOAD QUANTITY	CUMULATIVE QUANTITY	ORDERED QUANTITY	MATERIAL CODE	PRODUCTION DESCRIPTION	UOM	UNIT PRICE	AMOUNT
7.50	7.50	7.50	1333049	TYPE II/V SLURRY 21 SK CNT/W YD3 LEGACY MATERIAL NO:			
1.00	1.00	1.00	1349968	SATURDAY OPENING	EA		
1.00			1247818	FUEL SURCHARGE ADJ.			
1.00			1202749	ENVIRONMENTAL FEE			
1.00			1572392	FREIGHT NON TAXABLE ARIZONA			

Comments:	WATER ADDED: _____ GAL		YARDS IN DRUM: _____
			WHEN ADDED.
	_____		SIGNATURE
	CURB LINE CROSSED AT OWNER'S/AGENT'S REQUEST:		
	_____		SIGNATURE
	<input type="checkbox"/> LOAD WAS TESTED	BY: _____	

**SPECIAL TERMS:** Any water added is at customers own risk. If water is added on job, concrete strength is no longer guaranteed. **WARNING:** Product may cause skin and/or eye irritation. **CAUTION:** Material may be hazardous to your safety and health. Please refer to the backside of this ticket for important safety handling information, and to the material safety data sheets for additional information.

ⓧ

## **APPENDIX E**

### **Geophysical Logs**



# Southwest Exploration Services, LLC

borehole geophysics & video services


COMPANY FLORENCE COPPER									
WELL ID M56-LBF									
FIELD FLORENCE COPPER									
COUNTY PINAL STATE ARIZONA									
TYPE OF LOGS: GAMMA - CALIPER									
MORE: TEMP / FLUID RES.									
LOCATION									
OTHER SERVICES									
CALIPER									
TEMP / FLUID RES.									
SONIC									
DEVIATION									
SEC TWP RGE									
PERMANENT DATUM ELEVATION									
LOG MEAS. FROM GROUND LEVEL ABOVE PERM. DATUM									
DRILLING MEAS. FROM GROUND LEVEL									
G.L.									
DATE 04-14-17									
FORMATION WATER									
RUN No 2									
MUD WEIGHT									
N/A									
TYPE LOG									
E-LOG - GAMMA									
VISCOSITY									
N/A									
DEPTH-DRILLER									
352.0 FT									
LEVEL									
SURFACE									
DEPTH-LOGGER									
352.0 FT									
MAX. REC. TEMP.									
32.2 DEG C									
BTM LOGGED INTERVAL									
352.0 FT									
IMAGE ORIENTED TO:									
N/A									
TOP LOGGED INTERVAL									
SURFACE									
SAMPLE INTERVAL									
0.2 FT									
DRILLER / RIG#									
NATIONAL DRILLING									
LOGGING TRUCK									
TRUCK #310									
RECORDED BY / Logging Eng.									
E. BEAM / K. MITCHELL									
TOOL STRING/SN									
ALT E-LOG IP SN 4784									
WITNESSED BY									
CHAD - H & A									
LOG TIME:ON SITE/OFF SITE									
7:00 AM									
RUN BOREHOLE RECORD									
CASING RECORD									
NO. BIT FROM TO									
SIZE									
WGT.									
FROM									
TO									
1 ? SURFACE 40 FT 14 IN STEEL SURFACE 40 FT									
2 10 5/8 IN 40 FT TOTAL DEPTH									
3									
COMMENTS:									


E-Log Calibration Range: 1 - 1,000 OHM-M      Calibration Points: 1 & 1,000 OHM-M

USED ABI40 IN PLACE OF DEVIATION TOOL. SAME DEVIATION PACKAGE IN BOTH TOOLS SO EITHER WILL WORK FOR A DEVIATION SURVEY

**Disclaimer:**

All interpretations of log data are opinions based on inferences from electrical or other measurements. We do not guarantee the accuracy or correctness of any interpretations or recommendations and shall not be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by anyone resulting from any interpretation made by any of our employees or agents. These interpretations are also subject to our general terms and conditions set out in our current Service Invoice.







<div>-----</div> <div>SP</div>			1in:20ft	<div>-----</div> <div>16" NRes</div>				
0	API	200		0	Ohm-m	50	0	Ohms
<div>-----</div> <div>Nat. Gamma</div>			Depth	<div>-----</div> <div>8" NRes</div>		<div>-----</div> <div>SPR</div>		

## ALT QL E-Log IP Tool

Probe Top = Depth Ref.

Tool SN: 4992, 4784 & 6041

Bridle connects to wireline cablehead: Wireline armor is the B Electrode.



64" Normal Resistivity Electrode/Spontaneous Potential Electrode (M Electrode)

Probe Length = 1.89 m or 6.2 ft  
Bridle Length = 7.88 m or 25.86 ft

Probe Weight = 8.8 kg or 19.4 lbs

Can only be collected in fluid  
May be stacked with other QL tools  
Has an Induced Polarization (IP) mode available

Operating Temperature: 80 Deg C (176 Deg F)  
Pressure Rating: 200 bar (2900 psi)

32" Normal Resistivity Electrode (M Electrode)


Electrode Measuring Points (from bottom of probe)  
Spontaneous Potential (SP): 1.689 m or 5.54 ft  
8" Normal Resistivity (8" NRes): 0.164 m or 0.54 ft  
16" Normal Resistivity (16" NRes): 0.266 m or 0.87 ft  
32" Normal Resistivity (32" NRes): 0.469 m or 1.54 ft  
64" Normal Resistivity (64" NRes): 0.875 m or 2.87 ft  
Single Point Resistance (SPR): 0.063 m or 0.21 ft

16" Normal Resistivity Electrode (M Electrode)

Isolation Bridle

8" Normal Resistivity Electrode (M Electrode)

Bridle Electrode (N Electrode)



1.63" or 40 mm Diameter (41.4 mm with neoprene heat shrink and electrical tape)

## MSI Gamma-Caliper-Temperature-Fluid Resistivity SN 4953

Probe Top = Depth Ref.



Single Conductor MSI Probe Top

Probe Length = 2.59 m or 8.5 ft

Probe Weight = 6.80 kg or 15.0 lbs

Natural Gamma and Caliper can only be collected logging up hole.

Fluid Temperature/Resistivity can only be collected logging down hole.

Temperature Rating: 70 Deg C (158 Deg F)

Pressure Rating: 200 bar (2900 psi)

Natural Gamma Ray = 0.76 m (29.75 in)

3-Arm Caliper = 1.44 m (56.75 in)

Distance from tool top: 2.20 m (86.5 in)

Available Arm Sizes: 3", 9", and 15"



TFR (Temperature/Fluid Resistivity) = 0.39 m (15.5 in)

1.375" or 34.9 mm Diameter



**Southwest Exploration  
Services, LLC**

borehole geophysics & video services

Company FLORENCE COPPER

Well M56-LBF

Field FLORENCE COPPER

County PINAL

State ARIZONA

**Final**

**E-Log Summary**



# Southwest Exploration Services, LLC


borehole geophysics & video services


COMPANY FLORENCE COPPER				
WELL ID	M56-LBF			
FIELD	FLORENCE COPPER			
COUNTY	PINAL			
STATE	ARIZONA			
TYPE OF LOGS: GAMMA - CALIPER				
MORE: TEMP / FLUID RES.				
LOCATION	OTHER SERVICES E-LOGS SONIC DEVIATION			
SEC	TWP	RGE		
PERMANENT DATUM			ELEVATION	K.B.
LOG MEAS. FROM	GROUND LEVEL	ABOVE PERM. DATUM	D.F.	
DRILLING MEAS. FROM	GROUND LEVEL	G.L.		
DATE	04-14-17	TYPE FLUID IN HOLE	FORMATION WATER	
RUN No	1	MUD WEIGHT	N/A	
TYPE LOG	GAMMA-CALIPER-TFR	VISCOSITY	N/A	
DEPTH-DRILLER	352.0 FT	LEVEL	SURFACE	
DEPTH-LOGGER	352.0 FT	MAX. REC. TEMP.	32.2 DEG C	
BTM LOGGED INTERVAL	352.0 FT	IMAGE ORIENTED TO:	N/A	
TOP LOGGED INTERVAL	SURFACE	SAMPLE INTERVAL	0.1 FT	
DRILLER / RIG#	NATIONAL DRILLING	LOGGING TRUCK	TRUCK #310	
RECORDED BY / Logging Eng.	E. BEAM / K. MITCHELL	TOOL STRING/SN	MSI COMBO TOOL SN 4953	
WITNESSED BY	CHAD - H & A	LOG TIME:ON SITE/OFF SITE	7:00 AM	
RUN				
BOREHOLE RECORD				
NO.	BIT	FROM	TO	CASING RECORD
		SIZE	WGT.	FROM
1	?	SURFACE	40 FT	14 IN
2	10 5/8 IN	40 FT	TOTAL DEPTH	
3				
COMMENTS:				

E-Log Calibration Range: 1 - 1,000 OHM-M      Calibration Points: 1 & 1,000 OHM-M  
USED ABI40 IN PLACE OF DEVIATION TOOL. SAME DEVIATION PACKAGE IN BOTH TOOLS SO EITHER WILL WORK FOR A DEVIATION SURVEY

**Disclaimer:**

All interpretations of log data are opinions based on inferences from electrical or other measurements. We do not guarantee the accuracy or correctness of any interpretations or recommendations and shall not be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by anyone resulting from any interpretation made by any of our employees or agents. These interpretations are also subject to our general terms and conditions set out in our current Service Invoice.







# MSI Gamma-Caliper-Temperature-Fluid Resistivity SN 4953

Probe Top = Depth Ref.



Single Conductor MSI Probe Top

Probe Length = 2.59 m or 8.5 ft

Probe Weight = 6.80 kg or 15.0 lbs

Natural Gamma and Caliper can only be collected logging up hole.

Fluid Temperature/Resistivity can only be collected logging down hole.

Temperature Rating: 70 Deg C (158 Deg F)

Pressure Rating: 200 bar (2900 psi)


Natural Gamma Ray = 0.76 m (29.75 in)

3-Arm Caliper = 1.44 m (56.75 in)

Distance from tool top: 2.20 m (86.5 in)

Available Arm Sizes: 3", 9", and 15"

TFR (Temperature/Fluid Resistivity) = 0.39 m (15.5 in)



1.375" or 34.9 mm Diameter



**Southwest Exploration  
Services, LLC**

borehole geophysics & video services

Company

FLORENCE COPPER

Well

M56-LBF

Field

FLORENCE COPPER

County

PINAL

State

ARIZONA

**Final**

**GCT Summary**



# Southwest Exploration Services, LLC

borehole geophysics & video services

COMPANY FLORENCE COPPER			
WELL ID M56-LBF		FIELD FLORENCE COPPER	
COUNTY	PINAL	STATE ARIZONA	
TYPE OF LOGS: 60MM SONIC MORE: GAMMA - CALIPER		OTHER SERVICES E-LOGS TEMP / FLUID RES DEVIATION	
LOCATION			
PERMANENT DATUM	SEC	TWP	RGE
LOG MEAS. FROM	GROUND LEVEL	ABOVE PERM. DATUM	K.B. D.F.
DRILLING MEAS. FROM	GROUND LEVEL		G.L.
DATE	04-14-17	TYPE FLUID IN HOLE	FORMATION WATER
RUN No	3	MUD WEIGHT	N/A
TYPE LOG	SONIC-GAMMA-CALIPER	VISCOSITY	N/A
DEPTH-DRILLER	352.0 FT	LEVEL	SURFACE
DEPTH-LOGGER	352.0 FT	MAX. REC. TEMP.	32.2 DEG C
BTM LOGGED INTERVAL	352.0 FT	IMAGE ORIENTED TO:	N/A
TOP LOGGED INTERVAL	SURFACE	SAMPLE INTERVAL	0.25 FT
DRILLER / RIG#	NATIONAL DRILLING	LOGGING TRUCK	TRUCK #310
RECORDED BY / Logging Eng.	E. BEAM / K. MITCHELL	TOOL STRING/SN	MSI 60MM SONIC SN 6003
WITNESSED BY	CHAD - H & A	LOG TIME:ON SITE/OFF SITE	7:00 AM
RUN	BOREHOLE RECORD		CASING RECORD
NO.	BIT	FROM	TO
1	?	SURFACE	40 FT
2	10 5/8 IN	40 FT	TOTAL DEPTH
3			
COMMENTS:			


<b>Tool Summary:</b>					
Date	04-14-17	Date	04-14-17	Date	04-14-17
Run No.	1	Run No.	2	Run No.	3
Tool Model	MSI COMBO TOOL	Tool Model	ALT E-LOG IP	Tool Model	MSI 60MM SONIC
Tool SN	4953	Tool SN	4784	Tool SN	6003
From	SURFACE	From	SURFACE	From	SURFACE
To	352.0 FT	To	352.0 FT	To	352.0 FT
Recorded By	E. BEAM	Recorded By	E. BEAM	Recorded By	E. BEAM
Truck No	310	Truck No	310	Truck No	310
Operation Check	04-12-17	Operation Check	04-14-17	Operation Check	04-14-17
Calibration Check	04-12-17	Calibration Check	N/A	Calibration Check	N/A
Time Logged	10:10 AM	Time Logged	11:10 AM	Time Logged	11:30 AM
Date	04-14-17	Date		Date	
Run No.	4	Run No.	5	Run No.	6
Tool Model	ALT QL ABI40 2G	Tool Model		Tool Model	
Tool SN	143003	Tool SN		Tool SN	
From	SURFACE	From		From	
To	352.0 FT	To		To	
Recorded By	E. BEAM	Recorded By		Recorded By	
Truck No	310	Truck No		Truck No	
Operation Check	04-14-17	Operation Check		Operation Check	
Calibration Check	N/A	Calibration Check		Calibration Check	
Time Logged	11:50 AM	Time Logged		Time Logged	
<b>Additional Comments:</b>					
Caliper Arms Used: 9" Calibration Points: 6" & 12"					


E-Log Calibration Range: 1 - 1,000 OHM-M      Calibration Points: 1 & 1,000 OHM-M

USED ABI40 IN PLACE OF DEVIATION TOOL. SAME DEVIATION PACKAGE IN BOTH TOOLS SO EITHER WILL WORK FOR A DEVIATION SURVEY

**Disclaimer:**

All interpretations of log data are opinions based on inferences from electrical or other measurements. We do not guarantee the accuracy or correctness of any interpretations or recommendations and shall not be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by anyone resulting from any interpretation made by any of our employees or agents. These interpretations are also subject to our general terms and conditions set out in our current Service Invoice.





160.0

180.0

200.0

220.0

240.0

260.0

280.0

300.0

320.0


340.0

360.0

240 uSec/ft 40

**Delta T**

5 Inches 15



100 uSec

1000

100

uSec

1000

3-Arm Caliper			1in:20ft	RX1 - Travel Time			RX2 - Travel Time		
0	API	200		100	uSec	1000	100	uSec	1000
Nat. Gamma			Depth	RX1 - VDL			RX2 - VDL		

# MSI 60 mm 2 RX Full Waveform Sonic Tool

Probe Top = Depth Ref.

Tool SN: 5001, 5050 & 6003



Four Conductor MSI Probe Top

Probe Length = 2.8 m or 9.19 ft  
 Probe Weight = ~26.5 kg or 58.4 lbs

Sensors: Ceramic Piezoelectric

Transmitter Frequency: 24 - 28 kHz resonant frequency

Rx - Rx Spacing: 0.3 m (12.0 in)

Typically centralized with external centralizers

Can only be collected in fluid

Temperature Rating: 80 Deg C (176 Deg F)  
 Presure Rating: 200 bar (2900 psi)

Rx-2 Tx - Rx2 Spacing = 1.22 m (48.0 in)

Rx-1 Tx - Rx1 Spacing = .91 m (36.0 in)

Acoustic Isolater

Tx = Acoustic Transmitter





0.660 m or 26.0 in. - End of tool to center of Tx

2.36 in or 60 mm Diameter

## MSI Gamma-Caliper-Temperature-Fluid Resistivity SN 4953

Probe Top = Depth Ref.



Single Conductor MSI Probe Top

Probe Length = 2.59 m or 8.5 ft

Probe Weight = 6.80 kg or 15.0 lbs

Natural Gamma and Caliper can only be collected logging up hole.

Fluid Temperature/Resistivity can only be collected logging down hole.

Temperature Rating: 70 Deg C (158 Deg F)


Pressure Rating: 200 bar (2900 psi)

Natural Gamma Ray = 0.76 m (29.75 in)

3-Arm Caliper = 1.44 m (56.75 in)

Distance from tool top: 2.20 m (86.5 in)

Available Arm Sizes: 3", 9", and 15"



TFR (Temperature/Fluid Resistivity) = 0.39 m (15.5 in)

1.375" or 34.9 mm Diameter



**Southwest Exploration  
Services, LLC**

borehole geophysics & video services

Company FLORENCE COPPER

Well M56-LBF

Field FLORENCE COPPER

County PINAL

State ARIZONA

**Final**

**Sonic Summary**




# Southwest Exploration Services, LLC


borehole geophysics & video services

COMPANY FLORENCE COPPER									
WELL ID M56-LBF									
FIELD FLORENCE COPPER									
COUNTY PINAL STATE ARIZONA									
TYPE OF LOGS: VOLUME CALCULATION									
MORE: BASED ON 5.5" CASING									
LOCATION									
OTHER SERVICES									
E-LOGS									
SONIC									
DEVIATION									
GAMMA									
TEMP / FLUID RES									
SEC TWP RGE									
PERMANENT DATUM ELEVATION									
LOG MEAS. FROM GROUND LEVEL ABOVE PERM. DATUM									
DRILLING MEAS. FROM GROUND LEVEL									
G.L.									
DATE 04-14-17									
TYPE FLUID IN HOLE									
FORMATION WATER									
RUN No 1									
MUD WEIGHT									
N/A									
TYPE LOG									
GAMMA-CALIPER-TFR									
VISCOSITY									
N/A									
DEPTH-DRILLER									
352.0 FT									
LEVEL									
SURFACE									
DEPTH-LOGGER									
352.0 FT									
MAX. REC. TEMP.									
32.2 DEG C									
BTM LOGGED INTERVAL									
352.0 FT									
IMAGE ORIENTED TO:									
N/A									
TOP LOGGED INTERVAL									
SURFACE									
SAMPLE INTERVAL									
0.1 FT									
DRILLER / RIG#									
NATIONAL DRILLING									
LOGGING TRUCK									
TRUCK #310									
RECORDED BY / Logging Eng.									
E. BEAM / K. MITCHELL									
TOOL STRING/SN									
MSI COMBO TOOL SN 4953									
WITNESSED BY									
JEFF - H & A									
LOG TIME:ON SITE/OFF SITE									
7:00 AM									
RUN BOREHOLE RECORD									
CASING RECORD									
NO. BIT FROM TO									
SIZE									
WGT.									
FROM									
TO									
1 ? SURFACE 40 FT 14 IN STEEL SURFACE 40 FT									
2 10 5/8 IN 40 FT TOTAL DEPTH									
3									
COMMENTS:									

E-Log Calibration Range: 1 - 1,000 OHM-M Calibration Points: 1 & 1,000 OHM-M  
USED ABI40 IN PLACE OF DEVIATION TOOL. SAME DEVIATION PACKAGE IN BOTH TOOLS SO EITHER WILL WORK FOR A DEVIATION SURVEY

**Disclaimer:**  
All interpretations of log data are opinions based on inferences from electrical or other measurements. We do not guarantee the accuracy or correctness of any interpretations or recommendations and shall not be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by anyone resulting from any interpretation made by any of our employees or agents. These interpretations are also subject to our general terms and conditions set out in our current Service Invoice.





# MSI Gamma-Caliper-Temperature-Fluid Resistivity SN 4953

Probe Top = Depth Ref.



Single Conductor MSI Probe Top

Probe Length = 2.59 m or 8.5 ft

Probe Weight = 6.80 kg or 15.0 lbs

Natural Gamma and Caliper can only be collected logging up hole.

Fluid Temperature/Resistivity can only be collected logging down hole.

Temperature Rating: 70 Deg C (158 Deg F)

Pressure Rating: 200 bar (2900 psi)



Natural Gamma Ray = 0.76 m (29.75 in)



3-Arm Caliper = 1.44 m (56.75 in)

Distance from tool top: 2.20 m (86.5 in)



Available Arm Sizes: 3", 9", and 15"

TFR (Temperature/Fluid Resistivity) = 0.39 m (15.5 in)



1.375" or 34.9 mm Diameter



**Southwest Exploration  
Services, LLC**

borehole geophysics & video services

Company

FLORENCE COPPER

Well

M56-LBF

Field

FLORENCE COPPER

County

PINAL

State

ARIZONA

**Final**

**Caliper w/ Volume Calculation Summary**

# *Drift Report*

## Wellbore DRIFT Interpretation

PREPARED ESPECIALLY FOR  
**FLORENCE COPPER and FLORENCE COPPER**  
**M56-LBF**

Friday - April 14, 2017



This Wellbore Interpretation Package represents our best efforts to provide a correct interpretation. Nevertheless, since all interpretations are opinions based on inferences from electrical or other types of measurements, we cannot and do not guarantee the accuracy or correctness of any interpretation, and we shall not be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by Customer resulting from any interpretation made by this document. We do not warrant or guarantee the accuracy of the data, specifically including (but without limitations) the accuracy of data transmitted by electronic process, and we will not be responsible for accidental or intentional interception of such data by third parties. Our employees are not empowered to change or otherwise modify the attached interpretation. Furthermore, along with Eagle Pro Software we do not warrant or guarantee the accuracy of the programming techniques employed to produce this document. By accepting this Interpretation Package, the Customer agrees to the foregoing, and to our General Terms and Conditions.

**Southwest Exploration Services, LLC**  
**(480) 926-4558**

# WELLBORE DRIFT INTERPRETATION

Southwest Exploration Services, LLC

(480) 926-4558

Company:	FLORENCE COPPER			Well Owner:	FLORENCE COPPER							
County:	PINAL	State:	Arizona		Country:	United States						
Well Number:	M56-LBF		Survey Date:	Friday - April 14, 2017		Magnetic Declination:	Declination Correction Not Used					
Field:	FLORENCE COPPER		Drift Calculation Methodology:		Balanced Tangential Method							
Location:	FLORENCE COPPER											
Remarks:												
Witness:	CHAD - H & A	Vehicle No.:	310	Invoice No.:		Operator:	E. BEAM	Well Depth:	352 Feet	Casing size:	10 Inches	
Tool:	Compass - 143003		Lat.:		Long.:		Sec.:		Twp.:		Rge.:	

MEASURED DATA			DATA COMPUTATIONS						
DEPTHS, feet	INCLINATIONS, degrees	AZIMUTHS, degrees	TVD, feet	T. LATITUDE, feet	T. LONGITUDE, feet	DOGLEG SEV., degrees per 20 Feet	DOGLEG SEV., degrees per 100 feet	DRIFT DIST., feet	DRIFT BGR., degrees
5	0.32	020.14	5.00						
25	0.36	020.14	24.99	0.111	0.041	0.95	0.00	0.12' (1.44")	020.10
45	0.50	020.14	44.98	0.252	0.093	0.95	0.00	0.27' (3.24")	020.20
65	0.40	018.18	64.97	0.400	0.145	0.52	0.05	0.43' (5.16")	019.90
85	0.32	016.64	84.96	0.520	0.183	0.33	0.04	0.55' (6.60")	019.40
105	0.34	343.88	104.95	0.631	0.183	0.96	0.83	0.66' (7.92")	016.10
125	0.30	014.68	124.94	0.739	0.180	0.20	0.78	0.76' (9.12")	013.70
145	0.40	020.94	144.93	0.855	0.218	0.28	0.16	0.88' (10.56")	014.30
165	0.62	091.62	164.92	0.917	0.351	1.00	1.70	0.98' (11.76")	020.90
185	0.68	043.16	184.91	1.001	0.540	0.67	1.21	1.14' (13.68")	028.40
205	0.32	126.38	204.90	1.054	0.666	0.89	1.95	1.25' (15.00")	032.30
225	0.20	100.34	224.89	1.015	0.745	0.51	0.66	1.26' (15.12")	036.30
245	0.14	238.72	244.88	0.996	0.758	0.85	2.75	1.25' (15.00")	037.30
265	0.18	177.42	264.87	0.952	0.739	0.35	1.50	1.20' (14.40")	037.80
285	0.18	296.44	284.86	0.935	0.712	0.99	2.53	1.18' (14.16")	037.30
305	0.22	289.48	304.85	0.962	0.648	0.95	0.18	1.16' (13.92")	034.00
325	0.24	274.96	324.84	0.978	0.570	0.82	0.37	1.13' (13.56")	030.20
345	0.36	121.46	344.83	0.949	0.582	0.91	2.86	1.11' (13.32")	031.50

Page No. 1

True Vertical Depth: 344.83'

Final Drift Distance: 1.11' (13.32")

Final Drift Bearing: 31.50°

Note: Magnetic Declination is not used because it is not a factor in the calculation of well drift or alignment. Magnetic Declination is only important if attempting to hit a target or miss another well and then it is included in the calculations.

# PLANE OF DRIFT VIEW - M56-LBF

FLORENCE COPPER

FLORENCE COPPER

Drift Distance = 1.11 Feet

Drift Bearing = 31.5 Degrees

True Vertical Depth = 344.83 Feet



Date of Survey: Friday - April 14, 2017

Balanced Tangential Calculation Method

Southwest Exploration Services, LLC (480) 926-4558

# 3D PROJECTION VIEW - M56-LBF

FLORENCE COPPER


FLORENCE COPPER

Drift Distance = 1.11 Feet

Drift Bearing = 31.5 Degrees

True Vertical Depth = 344.83 Feet

6.0



Date of Survey: Friday - April 14, 2017

Balanced Tangential Calculation Method

Southwest Exploration Services, LLC (480) 926-4558

# POLAR VIEW - M56-LBF


FLORENCE COPPER

FLORENCE COPPER

Drift Distance = 1.11 Feet

Drift Bearing = 31.5 Degrees

True Vertical Depth = 344.83 Feet



Date of Survey: Friday - April 14, 2017

Balanced Tangential Calculation Method

Southwest Exploration Services, LLC (480) 926-4558




# EASTING RECTANGULAR VIEW - M56-LBF

FLORENCE COPPER  
FLORENCE COPPER

Drift Distance = 1.11 Feet

Drift Bearing = 31.5 Degrees

True Vertical Depth = 344.83 Feet



Date of Survey: Friday - April 14, 2017

Balanced Tangential Calculation Method

Southwest Exploration Services, LLC (480) 926-4558


# NORTHING RECTANGULAR VIEW - M56-LBF

FLORENCE COPPER  
FLORENCE COPPER

Drift Distance = 1.11 Feet

Drift Bearing = 31.5 Degrees

True Vertical Depth = 344.83 Feet



Date of Survey: Friday - April 14, 2017

Balanced Tangential Calculation Method

Southwest Exploration Services, LLC (480) 926-4558

## **APPENDIX F**

### **SAPT Documentation**

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
STANDARD ANNULAR PRESSURE TEST

Operator FLORENCE COPPER, INC

State Permit No. P-101704

Address 1575 W. HUNT HWY

USEPA Permit No. R9UIC-AZ3-FY11-1

FLORENCE, AZ 85132

Date of Test 6/28/2017

Well Name M56-LBF

Well Type CLASS III - SUPPL. MONITORING

**LOCATION INFORMATION**

SE Quarter of the NW Quarter of the SW Quarter  
of Section 28 ; Range 9E ; Township 4S ; County PINAL ;

Company Representative IAN REAM ; Field Inspector LAUREN CANDREVA ;

Type of Pressure Gauge Pressure transducer with data logger inch face; 300 psi full scale; 0.001 psi increments;

New Gauge? Yes ☒ No ☐ If no, date of calibration            Calibration certification submitted? Yes ☐ No ☒

**TEST RESULTS**

Readings must be taken at least every 10 minutes for a minimum of 30 minutes for Class II, III and V wells and 60 minutes for Class I wells.

For Class II wells, annulus pressure should be at least 300 psig. For Class I wells, annulus pressure should be the greater of 300 psig or 100 psi above maximum permitted injection pressure.

Original chart recordings must be submitted with this form.

5-year or annual test on time? Yes ☐ No ☒

2-year test for TA'd wells on time? Yes ☐ No ☒

After rework? Yes ☐ No ☒

Newly permitted well? Yes ☒ No ☐

Time	Pressure (in psig)	
	Annulus	Tubing
17:38	126.87	same
17:46	120.53	same
17:56	114.52	same
18:06	109.42	same
18:11	107.01	same

Casing size 5" - NOMINAL

Tubing size 2"

Packer type INFLATABLE PACKER

Packer set @ 286.06

Top of Permitted Injection Zone NONE

Is packer 100 ft or less above top of

Injection Zone ? Yes ☐ No ☒

If not, please submit a justification.

Fluid return (gal.) NOT MEASURED

Comments: Monitoring well - completed approximately 120 feet above permitted injection zone.

Test Pressures: Max. Allowable Pressure Change: Initial test pressure x 0.05 6.34 psi  
Test Period Pressure change 19.86 psi

Test Passed ☐ Test Failed ☒

If failed test, well must be shut in, no injection can occur, and USEPA must be contacted within 24 hours. Corrective action needs to occur, the well retested, and written authorization received before injection can recommence.


I certify under penalty of law that this document and all attachments are, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. (See 40 CFR 144.32(d))

Ian Ream  
Printed Name of Company Representative

[Signature]  
Signature of Company Representative

9-14-2018  
Date

M60-O Standard Annular Pressure Test Data



Well M56-LBF SAPT Data		
Tranducer Serial Number:	519257	
Tranducer Model:	Level TROLL 400 non-vented 300 psi	
Date and Time	Pressure (PSI)	Corrected Presssure (PSI) (Sensor pressure - barometric pressure)
6/28/2017 17:37	15.243	0
6/28/2017 17:38	142.112	126.869
6/28/2017 17:39	141.091	125.848
6/28/2017 17:40	140.21	124.967
6/28/2017 17:41	139.37	124.127
6/28/2017 17:42	138.632	123.389
6/28/2017 17:43	137.905	122.662
6/28/2017 17:44	137.184	121.941
6/28/2017 17:45	136.517	121.274
6/28/2017 17:46	135.769	120.526
6/28/2017 17:51	132.622	117.379
6/28/2017 17:56	129.759	114.516
6/28/2017 18:01	127.169	111.926
6/28/2017 18:06	124.661	109.418
6/28/2017 18:11	122.253	107.01
6/28/2017 18:16	119.883	104.64
6/28/2017 18:21	117.56	102.317
6/28/2017 18:26	115.289	100.046
6/28/2017 18:31	113.119	97.876
6/28/2017 18:36	110.938	95.695



## **APPENDIX G**

### **Cement Bond Log Summary**

WELL M56-LBF

Geophysical Log Summary





**Southwest Exploration Services, LLC**  
borehole geophysics & video services




COMPANY: FLORENCE COPPER COMPANY  
FIELD: FLORENCE COPPER SITE  
WELL ID: M56-LBF  
COUNTY: PINAL STATE: ARIZONA

Logging Engineer: VARIOUS  
Date Logged: VARIOUS  
Processed By: K.M / B.C.  
Date Processed: 09-09-18







## **APPENDIX H**

### **Well Development Forms**



# DEVELOPMENT FIELD DATA LOG

Project Name: <b>FCT</b>	Project No.: <b>129687-002</b>
Well No.: <b>M56-LBF</b>	Date: <b>4-21-17</b>
Location:	Measuring Point:
Total Depth of Well (ft bls): <b>340</b>	Screen Interval (ft bls): <b>420-340-320</b>
Pump Type/Setting (ft bls): <b>Grundfos AirLift, 320'</b>	Activity: <b>AirLift</b>
How Q Measured:	H&A Personnel: <b>C Price</b>

	Time	Discharge (gpm)	Pumping Water Level (ft)	Specific Capacity (gpm/ft)	Sand Content (ppm)	pH	Sp. Cond. (µmhos/cm)	Temp. °C	Comments
	1200								airlift compressor on
									No H&A at rig during airlift.
	1530								Airlift off
4-24-17	0600								Airlift on
	0630	~10			0.1				Brown,
	0700	10			<0.1				Brown
	0800	10			<0.1				light brown, put airlift off.
	0815	10							inject 1 gal aqua-clean
	0820								sub screen, ~15 min
4-25-17	1600								Premie @ 330'
	1620								Air on
	1622	~10			0.1				Brown,
	1730	10			0				light brown cloudy
	1745								off
4-26-17	0609								on
	0630	10			0				light brown, turbid
	0655	10							light brown, cloudy
	0700	10							turn air off
									End airlift.
Comments:									



# DEVELOPMENT FIELD DATA LOG

Project Name: FCI	Project No.: 129687-002
Well No.: M56-LBF	Date: 4-26-17 through 5-1-17
Location:	Measuring Point: top of monument, 2.25' a/s
Total Depth of Well (ft bls): 340	Screen Interval (ft bls): 340-320
Pump Type/Setting (ft bls): Grundfos, 335'	Activity: Development
How Q Measured: stopwatch / 5 gal bucket	H&A Personnel: C Price

Time	Discharge (gpm)	Pumping Water Level (ft)	Specific Capacity (gpm/ft)	Sand Content (ppm)	pH	Sp. Cond. (µmhos/cm)	Temp. °C	Comments	NTU
0854		236.24							
0900		236.25						pump on	
0902	19	267.89		<0.1	6.68	1410	23.6	light brown	OR
0906	19	304.44		<0.1	6.87	1408	23.8	light brown	OR
0910	19	322.42		0.2	6.94	1416	23.1	"	OR
0915	19	328.74		0.6	7.12	1419	22.9	Brown	OR
0920	19	320.08		0.1	7.12	1415	23.7	light brown	OR
0925	19	313.82		0.1	7.11	1410	23.4	cloudy	261
0930	19	311.13		<0.1	7.13	1407	23.2	cloudy	144
1100	19	313.71		0	7.34	1410	24.0	slightly cloudy	40
1120	19	313.70		0	7.27	1404	23.9	clear	23.0
1230	19	314.62		0	7.33	1438	23.9	clear	11.5
1235	19	314.56		0	7.29	1411	23.5	clear	13.9
1240	19	314.63		0	7.25	1412	23.6	clear	11.9
1245								pump off	
1330		236.41						pump on	
1332	19	261.89		<0.1	7.30	1423	24.7	brown, cloudy	534
1336	19	282.26		<0.1	7.33	1430	25.9	brown, turbid	908
1340	19	292.55		0.1	7.32	1408	23.4	brown, turbid	478
1345	19	297.58		0.1	7.34	1418	23.9	brown, turbid	384
1400	19	303.94		<0.1	7.29	1409	23.5	brown, turbid	267
1415	19	308.00		0.1	7.26	1402	24.0	light brown, cloudy	158
1432	19	308.28		<0.1	7.28	1399	24.0	cloudy	70.4
1600	19	308.64		<0.1	7.20	1401	24.8	clear	26.2
								pump off	
1620		236.90						pump on	
1623	19	261.00		<0.1	7.27	1412	25.0	cloudy	177
1628	19	286.98		<0.1	7.26	1402	24.0	cloudy-brown	798

Comments:



# DEVELOPMENT FIELD DATA LOG

Project Name: <u>FLI</u>	Project No.: <u>129687-002</u>
Well No.: <u>M56-LBF</u>	Date:
Location:	Measuring Point: <u>TOM 2.25' a/s</u>
Total Depth of Well (ft bls): <u>340</u>	Screen Interval (ft bls): <u>340-320</u>
Pump Type/Setting (ft bls): <u>Grundfos 335'</u>	Activity: <u>Development</u>
How Q Measured:	H&A Personnel: <u>C Price</u>

Time	Discharge (gpm)	Pumping Water Level (ft)	Specific Capacity (gpm/ft)	Sand Content (ppm)	pH	Sp. Cond. (µmhos/cm)	Temp. °C	Comments
1633	19	297.22		<0.1	7.27	1407	23.4	cloudy NTU 417
1728	19	310.99		<0.1	7.33	1401	23.4	clear 88.7
1744	19	314.29		<0.1	7.30	1407	23.0	clear/cloudy 116
0604		235.94						
0607	19	267.02		0.1	6.56	1414	21.9	cloudy 133
0610	19	277.89		<0.1	6.74	1413	22.0	light brown 889
0618	19	293.08		0.1	6.93	1406	22.0	light brown 609
0640	19	298.41		<0.1	6.98	1404	21.9	clear 63.2
0703	19	300.38		<0.1	7.01	1400	22.1	clear 59.6
0733	19	303.92		<0.1	6.97	1399	22.3	clear 49.0
0809	19	303.25		<0.1	7.09	1397	22.7	clear 19.1
0825	19	303.07		0	7.21	1403	22.7	clear 9.97
0827								pump off
0916		236.20						pump on
0918	19	259.66		<0.1	7.19	1420	23.3	cloudy 98.5
0920	19	272.61		0.1	7.16	1412	23.0	light brown 632
0952	19	294.62		<0.1	7.21	1420	23.5	clear 36.6
1025	19	295.25		<0.1	7.18	1407	23.8	clear 22.4
1045	19	295.45		<0.1	7.20	1412	23.5	clear 13.7
1058								pump off
1100								pump on
1419	19	293.71		<0.1	7.32	1415	24.8	clear 6.38
1420								pump off
1428		234.50						pump on
1430	19	262.04		<0.1	7.25	1410	23.8	clear 4.90
1435	19	264.18		<0.1	7.24	1408	23.4	cloudy 641
1455	19	299.61		<0.1	7.25	1413	23.9	cloudy 369
Comments:								



# DEVELOPMENT FIELD DATA LOG

Project Name: <u>FCI</u>	Project No.: <u>129687-002</u>
Well No.: <u>M56-LBF</u>	Date:
Location:	Measuring Point: <u>TOM - 2.25'</u>
Total Depth of Well (ft bls): <u>340</u>	Screen Interval (ft bls): <u>340-320</u>
Pump Type/Setting (ft bls): <u>Grundfos 3351</u>	Activity: <u>Development</u>
How Q Measured:	H&A Personnel: <u>C Price &amp; C Giusti</u>

Time	Discharge (gpm)	Pumping Water Level (ft)	Specific Capacity (gpm/ft)	Sand Content (ppm)	pH	Sp. Cond. (umhos/cm)	Temp. °C	Comments	NTU
1513	19	299.78		<0.1	7.23	1411	24.0	cloudy	111
1528	19	299.71		<0.1	7.20	1409	23.9	clear	67.6
1535	19	299.31		<0.1	7.22	1412	23.5	clear	12.9
1545	19	299.24		<0.1	7.23	1411	23.3	clear	21.7
1547								pump off	
1633		231.71						pump on	
1637	19	263.72		<0.1	7.31	1411	23.4	cloudy	49.4
1700	19	289.89		<0.1	7.28	1405	23.2	clear	106
1715	19	293.64		<0.1	7.26	1402	23.0	clear	78.4
1736	19	296.18		0	7.26	1402	23.1	clear	42.6
1754	19	296.22		<0.1	7.25	1404	23.0	clear	17.4
1756								pump off	
4-28-17 1800								pump on	
610	19	270.9		0.75	6.85	1408	21.8	CLOUDY	32.0
630	19	278.3		0.1	7.04	1408	22.1	CLOUDY	90.0
700	19	279.1		<0.1	7.12	1402	22.4	clear	19.7
730	19	279.3		<0.1	7.18	1409	22.6	clear	10.6
800	19	279.6		<0.1	7.16	1402	22.5	clear	18.4
830	19	280.6		<0.1	7.19	1404	22.6	clear	18.9
900	19	281.0		0	7.19	1405	22.6	clear	14.2
930	19	281.0		0	7.20	1404	22.7	clear	5.38
1000	19	282.3			7.22	1414	22.9	clear	8.71
1005								pump off	
1116								pump on	
1115	19	269.7		0.2	7.25	1411	23.1	CLOUDY	255
1130	19	277.7		<0.1	7.20	1409	22.9	MILKY	46.4
1200	19	280.2		<0.1	7.24	1408	22.8	clear	17.0

Comments:



# DEVELOPMENT FIELD DATA LOG

Project Name: <u>FCI</u>	Project No.: <u>129087-002</u>
Well No.: <u>M56-LBF</u>	Date:
Location:	Measuring Point: <u>TOM 2.25'</u>
Total Depth of Well (ft bls): <u>340</u>	Screen Interval (ft bls): <u>340-320</u>
Pump Type/Setting (ft bls): <u>Grundfos, 335'</u>	Activity: <u>Development</u>
How Q Measured:	H&A Personnel: <u>C. Giusti</u>

Time	Discharge (gpm)	Pumping Water Level (ft)	Specific Capacity (gpm/ft)	Sand Content (ppm)	pH	Sp. Cond. (µmhos/cm)	Temp. °C	Comments	NTU
1230	19	282.0		0	7.25	1409	22.9	CLEAR	9.60
1300	19	282.3		0	7.30	1405	23.2	CLEAR	7.24
1305								PUMP OFF	
1405					7.36	1406	23.7	PUMP ON	
1410	19	261.3		0.03	7.31	1444	23.6	LIGHT BROWN 3m/L	339
1425	19	278.9		0.01	7.29	1409	23.6	MILKY	57.7
1440	19	280.7		<0.01	7.25	1416	23.4	MILKY/CLEAR	23.7
1500	19	281.2		20.01	7.26	1405	23.3	CLEAR	15.7
1530	19	282.7		0	7.26	1410	23.7	CLEAR	5.85
1535								PUMP OFF	
1605	19							PUMP ON	
1610	19	267.4		0.01	7.32	1403	23.6	CLOUDY/LTBROWN	396
1625	19	276.7		<0.01	7.21	1409	23.4	MILKY 3m/L	81.8
1640	19	277.4		<0.01	7.26	1405	23.1	CLEAR	10.7
1700	19	277.2		0	7.25	1404	23.4	CLEAR	43.8
1700								PUMP OFF	
1730								PUMP ON	
1735	19	277.0		0.01	7.27	1400	23.4	CLOUDY	224
1800	19	277.5		<0.01	7.29	1401	23.0	CLEAR	12.2
1805								PUMP OFF	
0830		235.38						pump on	
0834	19	262.42		<0.1	6.79	1434	23.1	clear	12.2
0837	19	275.15		<0.1	6.73	1436	23.2	cloudy	185
0840	19	277.14		<0.1	6.92	1435	22.9	clear	43.0
0850	19	279.44		0	7.07	1437	22.8	clear	19.4
0904	19	279.91		0	7.12	1425	23.7	clear	2.03
0914	19	279.99		<0.1	7.15	1435	22.8	clear	4.46
0915								pump off	
Comments:									



# DEVELOPMENT FIELD DATA LOG

Project Name: <u>FLI</u>	Project No.: <u>129687-002</u>
Well No.: <u>1156-LBF</u>	Date:
Location:	Measuring Point: <u>Tom 2.25' als</u>
Total Depth of Well (ft bls): <u>340</u>	Screen Interval (ft bls): <u>340-320</u>
Pump Type/Setting (ft bls): <u>Grundfos 335'</u>	Activity: <u>Development</u>
How Q Measured:	H&A Personnel: <u>C Price</u>

Time	Discharge (gpm)	Pumping Water Level (ft)	Specific Capacity (gpm/ft)	Sand Content (ppm)	pH	Sp. Cond. (µmhos/cm)	Temp. °C	Comments
1000		235.61						
1002	19	262.25		20.1	7.19	1451	23.4	pump on cloudy 138
1004	19	271.09		<0.1	7.17	1433	23.2	cloudy 236
1010	19	277.86		0	7.16	1427	23.2	clear 59.5
1020	19	279.96		0	7.14	1434	22.7	clear 38.1
1030	19	280.04		0	7.17	1437	23.2	clear 16.0
1040	19	280.18		0	7.17	1415	23.4	clear 12.4
1055	19	280.32		0	7.18	1423	22.9	clear 8.86
1057								pump off
1132		235.71						
1135	19	264.71		<0.1	7.22	1438	23.2	cloudy 53.5
1138	19	272.74		<0.1	7.19	1430	23.2	cloudy 219
1150	19	280.46		<0.1	7.19	1439	23.3	cloudy 88.2
1200	19	280.54		0	7.20	1430	23.2	clear 13.7
1210	19	280.66		0	7.18	1439	23.3	clear 2.80
1212								pump off
1245		235.80						pump on
1247	19	262.44		<0.1	7.22	1442	23.6	cloudy 238
1250	19	271.81		<0.1	7.20	1433	23.1	cloudy 376
1316	19	280.41		0	7.22	1431	23.4	clear 12.3
1318								pump off
1343		235.90						pump on
1346	19	260.04		<0.1	7.20	1440	23.7	cloudy 109
1348	19	270.66		<0.1	7.19	1429	23.2	cloudy 315
1423	19	260.54		0	7.24	1420	23.8	clear 9.65
1425								pump off
1442		236.04						pump on
1445	19	263.45		<0.1	7.21	1445	23.8	turbid 454

Comments:



# DEVELOPMENT FIELD DATA LOG

Project Name: <u>FLI</u>	Project No.: <u>129687-002</u>
Well No.: <u>M56-LBF</u>	Date:
Location:	Measuring Point: <u>Tom 2.25' a/s</u>
Total Depth of Well (ft bls): <u>340</u>	Screen Interval (ft bls): <u>340-320</u>
Pump Type/Setting (ft bls): <u>Grundfos, 335</u>	Activity: <u>Development</u>
How Q Measured:	H&A Personnel: <u>L Price</u>

Time	Discharge (gpm)	Pumping Water Level (ft)	Specific Capacity (gpm/ft)	Sand Content (ppm)	pH	Sp. Cond. (μmhos/cm)	Temp. °C	Comments
1447	19	273.04		<0.1	7.20	1433	23.3	cloudy 233
1505	19	280.56		70.1	7.21	1441	23.1	clear 26.9
1524		280.72		0	7.21	1440	23.2	clear 6.70
1525								pump off
1554	19	235.02						pump on
1650	19	262.66		<0.1	7.22	1451	23.5	cloudy 89.1
1558	19	271.14		<0.1	7.21	1431	23.4	turbid 281
1635	19	280.69		0	7.20	1440	23.1	clear 10.9
1713	19	281.46		0	7.26	1436	22.7	clear 7.44
1750	19	281.99		0	7.22	1430	23.1	clear 7.60
1751								pump off
4-30-17 0811	2	236.11						pump on
0814	19	263.32		<0.1	6.37	1430	22.6	Brown 335
0816	19	271.91		<0.1	6.66	1431	22.5	cloudy 342
0822	19	279.42		0	6.94	1428	22.8	cloudy 84.0
0831	19	281.21		0	7.02	1438	22.7	clear 33.9
0840	19	281.41		0	7.06	1428	22.9	clear 19.2
0852	19	281.38		0	7.09	1433	22.8	clear 11.4
0855								pump off
0930		236.29						pump on
0933	19	263.92		<0.1	7.18	1447	23.6	light brown 157
0935	19	272.38		<0.1	7.19	1428	23.4	brown 333
1009	19	280.18		0	7.23	1436	23.3	clear 9.18
1117	19	280.33		<0.1	7.33	1415	24.1	clear 2.26
1155	19	280.50		0	7.28	1427	23.9	clear 1.45
1320	19	280.66		0	7.26	1429	24.2	clear 1.08
1651	19	280.92		0	7.37	1434	23.9	clear 0.57

Comments:



## DEVELOPMENT FIELD DATA LOG

Project Name: FCI	Project No.: 129687-002
Well No.: NSG-LBF	Date: 5-1-17
Location:	Measuring Point: Top of monument, 2.25' ab
Total Depth of Well (ft bls): 340	Screen Interval (ft bls): 340-320
Pump Type/Setting (ft bls): Grundfos, 335'	Activity: Development
How Q Measured: Stop watch / 5 gal bucket	H&A Personnel: L Price

[illegible]

Comments: